



BENGALURU SOUTH CITY CORPORATION

TENDER DOCUMENT - KW4

(WORKS COSTING MORE THAN Rs. 100 LAKHS)

Name of Work: Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures to selected arterial, subarterial and other important roads under Capital Support for Special Infra Projects (CSSIP) (Comprising of 6 works in GO BSCC Sl no 22, 23, 24, 25, 26, 30) Package no CSSIP-UHD-03

Estimated Cost: 2997.00 Lakhs

CONTRACTOR

EXECUTIVE ENGINEER
UTTARAHALLI DIVISION

Contents

Section n No.	Description	Page
1	INVITATION FOR TENDERS (IFT)	
2	INSTRUCTIONS TO TENDERERS (ITT)	
3	QUALIFICATION INFORMATION	
4	FORM OF TENDER, LETTER OF ACCEPTANCE, NOTICE TO PROCEED WITH THE WORK AND AGREEMENT FORM	
5	CONDITIONS OF CONTRACT (CC)	
6	CONTRACT DATA	
7	SPECIFICATIONS	
8	DRAWINGS	
9	BILL OF QUANTITIES	
10	FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT	

CONTRACTOR

EXECUTIVE ENGINEER
UTTARAHALLI DIVISION



BENGALURU SOUTH CITY CORPORATION

Tender Notification No: EE/UHD/TEND/ 03 /2025-26

Office of the
Executive Engineer,
Uttarahalli Division,
Bengaluru South City
Corporation, Amruth
nagara-Konankunte
Main road, Soudamini
Layout, Bengaluru-62.
Dated : 17.11.2025

INVITATION FOR SHORT TERM TENDER

(Only through Karnataka Public Procurement Portal)

TWO COVER TENDER

1. The GOK vide G.O. No.UDD/475/MNY/2025(E), Bengaluru, Date:14-11-2025 has accorded in principle approval to the action plan for approval works pertaining to Bengaluru South City Corporation, Vide Annexure-5.
2. The Executive Engineer, Uttarahalli Division, Bengaluru South City Corporation, Bengaluru-560062 Invites tenders on behalf the Commissioner from eligible contractors registered with / KPWD/CPWD/BWSSB/ Railways/MES/National Highway or any state Government Organizations for the Construction of works detailed in the table below. The tenderers may submit tenders for works given in the table through Karnataka Public Procurement Portal of the Government of

CONTRACTOR

EXECUTIVE ENGINEER
UTTARAHALLI DIVISION

Karnataka (viz <https://kppp.karnataka.gov.in>). The Tenderers are advised to note the minimum qualification criteria specified in clause 3 of the instructions to Tenderers to qualify for award of the contract (Standard Tender Document - KW4)

3. Tenders must be accompanied by Earnest Money Deposit specified for the work in the table below. Earnest money deposit will have to be in any one of the forms as specified in the Tender document and shall have to be valid for 90 days beyond the validity of the Tender.
4. Tenders must be submitted online through Karnataka Public Procurement Portal on or before 16.00 hours on **05.12.2025** and the opening of tenders will be as per the Karnataka Public Procurement Portal guidelines.
5. Other details can be seen in the tender documents.

TABLE

Sl No	Name of the work	Approximate Amount Put to Tender (Rs in Lakhs)	EMD (Rs.in Lakhs)	Period Completion (Days) including monsoon period.	Category / Reserved for
1	2	3	4	5	6
1	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures to selected arterial, subarterial and other important roads under Capital Support for Special Infra Projects (CSSIP) (Comprising of 4 works in GO BSCC Sl no 16, 17, 28, 29) Package No CSSIP-UHD-01	2057.00	20.57	11 Months	Others
2	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures to selected arterial,	1873.00	18.73	11 Months	Others

CONTRACTOR

EXECUTIVE ENGINEER
UTTARAHALLI DIVISION

	subarterial and other important roads under Capital Support for Special Infra Projects (CSSIP) (Comprising of 5 works in GO BSCC Sl no 18, 19, 20, 21, 27) Package no CSSIP-UHD-02				
3	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures to selected arterial, subarterial and other important roads under Capital Support for Special Infra Projects (CSSIP) (Comprising of 6 works in GO BSCC Sl no 22, 23, 24, 25, 26, 30) Package no CSSIP-UHD-03	2387.00	23.87	11 Months	Others

Calendar of events:

- **Uploading of Tender Documents From 20.11.2025.**
- **Pre-bid Meeting 27.11.2025, will be held of the Office of The Chief Engineer [Jayanagara Zone-1], 9th Main, 9th Cross, Jayanagara 2nd Block, Bengaluru-11 at 3.00 P.M.**
- **Last Date for uploading the Filled Tender Document is 05.12.2025 upto 05.30 p.m.**
- **Date of Technical bid opening of Tenders is on 08.12.2025 after 11.00 a.m.**

Sd/-

Executive Engineer

Uttarahalli Division,

Bengaluru South City Corporation,

CONTRACTOR

EXECUTIVE ENGINEER
UTTARAHALLI DIVISION

Copy to:

1. The Commissioner, Bengaluru South City Corporation, Bengaluru for kind information.
2. The Joint Commissioner, (South-01), Bengaluru South City Corporation, Bengaluru for kind information.
3. The Chief Engineer, (South-01) Bengaluru South City Corporation, for kind information.
4. The Chief Accounts Officer, Bengaluru South City Corporation, for kind information.
5. To all Executive Engineer of all city corporation of Bengaluru for kind information & to notify this notification in their Office Notice Boards.
6. The Assistant Public Relation Officer, Bengaluru South City Corporation, to initiate necessary action to publish this Notification in leading News Papers of Bengaluru Edition and one each in Kannada & English as the case may be within next two days and give wide publicity to this notification and request to communicate the same to this office as early as possible for further action.
7. The Account Superintendent, Uttarahalli Division for information and further action regarding accepting requisition from Contractors and collection of Tender Documents from Technical Section and issue the same to the eligible Contractors.
8. The Revenue Officer/Store Keeper/Record Section. Mayo Hall, for information and needful action.
9. Cashier of Uttarahalli Division Office for needful.
10. To the IT Advisor, Bengaluru South City Corporation, to initiate necessary action to Publish this Tender Notification in the web-site (Soft copy in CD Format which is enclosed with this Notification).
11. To Office Notice Board.
12. To the Office Copy.

**Executive
Engineer
Uttarahalli Division,
Bengaluru South City
Corporation.**

SECTION 2: INSTRUCTIONS TO TENDERERS (ITT)

Table of Clauses

A. General

1. Scope of Tender

Page No.

CONTRACTOR

EXECUTIVE ENGINEER
UTTARAHALLI DIVISION

2. Eligible Tenderers
3. Qualification of the Tenderer
4. One Tender per Tenderer
5. Cost of Tendering
6. Site Visit

B. Tender Documents

7. Content of Tender documents
8. Clarification of Tender Document
9. Amendment of Tender documents

C. Preparation of Tenders

10. Documents comprising the Tender
11. Tender prices
12. Tender validity
13. Earnest money deposit
14. Format and signing of Tender

D. Submission of Tenders

15. Sealing and marking of Tenders
16. Deadline for submission of Tenders
17. Late Tenders
18. Modification and Withdrawal of Tenders

E. Tender opening and evaluation

19. Opening of First Cover of all Tenders and evaluation to determine qualified Tenderers
20. Opening of Second Cover Tenders of qualified Tenders and evaluation
21. Process to be confidential
22. Clarification of Tenders
23. Examination of Tenders and determination of responsiveness
24. Correction of errors
25. Evaluation and comparison of Tenders

F. Award of contract

26. Award criteria
27. Employer's right to accept any Tender and to reject any or all Tenders
28. Notification of award and signing of Agreement
29. Security deposit
30. Advance payment and Security
31. Corrupt or Fraudulent Practices

CONTRACTOR

EXECUTIVE ENGINEER
UTTARAHALLI DIVISION

A. General

1. Scope of Tender

The Executive Engineer, Uttarahalli Division, on behalf of the Commissioner Bengaluru south city Corporation (Referred to as Employer in these documents) invites tenders following Two Cover tender procedure, from eligible Tenderers, for the works of **"Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures to selected arterial, subarterial and other important roads under Capital Support for Special Infra Projects (CSSIP) (Comprising of 6 works in GO BSCC Sl no 22, 23, 24, 25, 26, 30) Package no CSSIP-UHD-03."** detailed in the Table given in the Invitation for Tenders (IFT). The Tenderers may submit tenders for any or all of the works detailed in the table given in IFT.

2. Eligible Tenderers

- 2.1 Tenderers shall not be under a declaration of ineligibility for corrupt and fraudulent practices issued by the Government of Karnataka.
- 2.2 **Tenders from Joint ventures are not acceptable.**

3. Qualification of the Tenderer:

- 3.1 All Tenderers shall provide the requested information accurately and sufficient details in Section 3: Qualification information.
- 3.2 To qualify for award of this contract, each Tenderer in its name should have in the last five years (i.e. 2020-21 to 2024-25) (Updated to the FY in which the tenders are invited. Financial turn over of previous years shall be given a weight of 10% per year to bring them to the price level of the FY in which the tenders are invited.)
- (a) Achieved a minimum financial turnover (in all classes of civil engineering construction works only) of **Rs. 4724.62** in at least two financial years. (usually not less than two times the estimated annual payments under this contract)
- (b) Satisfactory Completion as a prime Contractor for at least one similar work to an extent of 50% of the cost of the work of value not less than **Rs. 1181.15 Lakhs.**
- (c) executed in any one year, the following minimum quantities of work:

Quantity Requirement			
Sl No	Particulars	Unit	Qty

1	Concrete(PCC/RCC/any grade)	Cum	4420.15
2	Bituminous Mix(BC/DBM/BM/SMA)	Cum	6699.35
3	Wet Mix/GSB	Cum	4728.26
4	Interlock Pavers/cobble stone	Sqm	13078.7 2

3.3 Each Tenderer should further demonstrate:

(a) Availability by owning at least 50% of the required / specified key and critical equipment for this work and the remaining 50% can be deployed on lease / hire basis for all works provided the relevant documents (commitment agreements etc.) for availability for this work are furnished.

Item of Equipment	Requirement		Equipment Own in nos	Equipment Lease/Hire in nos
	No.	Capacity		
Batch Mix Plant (minimum capacity of 100-120 TPH)	1	100-120 TPH		1
Mechanical Paver finisher	1		1	
Static Road roller	1		1	
Vibratory Road Roller	4	8 to over 10 tonne	1	3
Excavators (JCB/Hitachi)	2		-	2
Tippers	6		3	3
Water tanker	3			3

(b) Liquid assets and /or availability of credit facilities of **no less than Rs.787.44 Lakhs** (Credit lines/ letter of credit/ certificates from banks for meeting the fund requirement etc. (usually 30% of the amount of

contract)

- 3.4 To qualify for a package of contracts made up of more than one item of the Works set out in the table in IFT, the Tenderer must also demonstrate having experience and resources to meet the aggregate of the qualifying criteria or have MoU with original Manufacturers having the requisite qualification for the individual contracts.
- 3.5 Experience and resources of sub-contractors of Tenderer shall not be taken into account in determining the Tenderer's compliance with the qualifying criteria except for other allied technical work such as electrical works and plumbing works. In such a case, sub-contractors shall comply with Clause 3.2 (b) and Clause 3.3 of ITT.
- 3.6 Tenderers who meet the above specified minimum qualifying criteria, will only be qualified, if the available tender capacity is more than the total tender value. The available tender capacity will be calculated as under:

Assessed available tender capacity = $(A*N*1.5 - B)$

Where,

A = Maximum value of works executed in any one year during the last five years taking into account the completed as well as works in progress (updated to FY 2020-21 price level)

N = Number of years prescribed for completion of the works for which tenders are invited.

B = Value, at FY 2020-21 price level, of existing commitments and on-going works to be completed during the next 12 months (period of completion of the works for which tenders are invited - excluding monsoon period)

Note: - The statements showing the value of existing commitment and ongoing works as well as the stipulated period of completion remaining for each of the works listed should be countersigned by the respective employer in charge, not below the rank of an Executive Engineer or equivalent.

- 3.7 Tenderers shall be immediately disqualified if they are found to have any or all of the below:
- ☐ made misleading or false representations in the forms, statements and attachments submitted in proof of the qualification requirements;
 - ☐ record of poor performance such as, but not limited to, abandoning the works, not properly completing the contract, inordinate delays in completion;

- ☐ litigation history;
- ☐ financial failures;
- ☐ participated in the previous Tender for the same work and had quoted unreasonably high tender prices and could not furnish rational justification.

4. One Tender per Tenderer

- 4.1 Each Tenderer shall submit only one tender for one package. A Tenderer who submits or participates in more than one Tender (other than as a sub-contractor or in cases of alternatives that have been permitted by the employer) will cause all the proposals with the Tenderer's participation to be disqualified.

5. Cost of Tendering

- 5.1 The Tenderer shall bear all costs associated with the preparation and submission of his tender, and the Employer will in no case be responsible and liable for those costs.

B. Tender documents

6. Site visit:

- 6.1 The Tenderer at his own responsibility and risk is encouraged to visit and examine the Site of Works and its surroundings and obtain all information that may be necessary for preparing the Tender and entering into a contract for construction of the Works. The cost of visiting the Site shall be at the Tenderer's own expense.

7. Content of Tender documents

- 7.1 The set of tender documents shall have all the Sections given in Page 2:
- 7.2 Both the sets should be completed and returned with the tender.

8. Clarification of Tender Documents

8.1 A prospective tenderer requiring any clarification of the tender documents may notify the Employer in writing or by cable (hereinafter "cable" includes telex and facsimile) at the Employer's address indicated in the invitation to tender. The Employer will respond to any request for clarification which he receives earlier than 15 days prior to the deadline for submission of tenders. Copies of the Employer's response will be forwarded to all purchasers of the tender documents, including a description of the enquiry but without identifying its source.

8.2 **Pre-tender meeting:**

8.2.1 The tenderer or his authorized representative is invited to attend a pre-tender meeting which will take place at office of the Chief Engineer [Jayanagara Zone-1], 9th Main, 9th Cross, Jayanagara 2nd Block, Bengaluru-11, Dated: 27.11.2025 at 3.00 P.M.

8.2.2 The purpose of the meeting will be to clarify issues and to answer questions on any matter that may be raised at that stage

8.2.3 The tenderer is requested to submit any questions in writing or by cable to reach the Employer not later than before 05.12.2025 5.00pm

8.2.4 Minutes of the meeting, including the text of the questions raised (without identifying the source of enquiry) and the responses given will be transmitted without delay to all purchasers of the tender documents. Any modification of the tender documents listed in Sub-Clause 7.1 which may become necessary as a result of the pre-tender meeting shall be made by the Employer exclusively through the issue of an Addendum pursuant to Clause 9 and not through the minutes of the pre-tender meeting.

8.2.5 Non-attendance at the pre-tender meeting will not be a cause for disqualification of a tenderer.

9. **Amendment of Tender documents**

9.1 Before the deadline for submission of tenders, the Employer may modify the tender documents by issuing addenda.

- 9.2 Any addendum thus issued shall be part of the tender documents and shall be communicated in writing or by cable to all the purchasers of the tender documents.
- 9.3 To give prospective Tenderers reasonable time in which to take an addendum into account in preparing their tenders, the Employer shall extend as necessary the deadline for submission of tenders, in accordance with Sub-Clause 16.2 below.

C. Preparation of Tenders

10. Documents comprising the Tender

- 10.1 The tender submitted by the Tenderer shall be in two covers and shall contain the documents as follows:

10.1.1 First Cover: AS PER E-PORTAL

- (a) Earnest Money Deposit;
- (a) Qualification Information as per formats given in Section 3;

10.1.2 Second Cover: AS PER E-PORTAL

- (a) The Tender (in the format indicated in Section 4)
- (b) Priced Bill of Quantities (Section 9);
- and any other materials required to be completed and submitted by Tenderers in accordance with these instructions. The documents listed under Sections 3, 4, 6 and 9 shall be filled in without exception.

- 10.2 Tenderers submitting tenders together with other contracts stated in the IFT to form a package will so indicate in the tender together with any discounts offered for the award of more than one contract

11. Tender prices

- 11.1 The contract shall be for the whole works as described in Sub-Clause 1.1, based on the priced Bill of Quantities submitted by the Tenderer.
- 11.2 The Tenderer shall fill in rates and prices and line item total (both in figures and words) for all items of the Works described in the Bill of Quantities along with total tender price (both in figures and words). **Items for which no rate or price is entered by the Tenderer will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities.** Corrections, if any, shall be made by crossing out, initialing, dating and rewriting.
- 11.3 All duties, taxes, and other levies payable by the contractor under the contract, or for any other cause, shall be included in the rates, prices and total Tender Price submitted by the Tenderer.
- 11.4 The rates and prices quoted by the Tenderer shall be subject to adjustment during the performance of the Contract in accordance with the provisions of Clause of the Conditions of Contract

12. Tender validity

- 12.1 Tenders shall remain valid for a period not less than 180 days after the deadline date for tender submission specified in Clause 16. A tender valid for a shorter period shall be rejected by the Employer as non-responsive.
- 12.2 In exceptional circumstances, prior to expiry of the original time limit, the Employer may request that the Tenderers may extend the period of validity for a specified additional period. The request and the Tenderers' responses shall be made in writing or by cable. A Tenderer may refuse the request without forfeiting his earnest money deposit. A Tenderer agreeing to the request will not be required or permitted to modify his tender, but will be required to extend the validity of his earnest money deposit for a period of the extension, and in compliance with Clause 13 in all respects.

13. Earnest money deposit

- 13.1 The Tenderer shall furnish, as part of his tender, Earnest Money Deposit (EMD) in the amount as mentioned in IFT for this particular Work. Further, out of the total EMD Amount Rs. 1.00 Lakh (Rupees One Lakh only) shall be paid in the e - procurement portal using any of the following modes and the Balance Amount shall be in the form of Bank Guarantee from any Nationalised / Scheduled Bank. A scanned copy of the same to be uploaded in the e-portal and the original to be submitted to this office before opening of tender.
- Credit Card.
 - Direct Debit.
 - National Electronic Fund Transfer (NEFT).
 - Over the Counter (OTC).

NEFT Payment Procedure

If a Tenderer chooses to make Payment of EMD / Tender Processing Fee using Reserve Bank of India's (RBI) National Electronic Fund Transfer (NEFT) System, the Tenderer will need to log into e - Procurement System, access the Tender for which Bid is being created and then select the NEFT Option under the Payment Section and print the Challan shown in that Section. The Printed Challan will have the Unique Bid Reference Number, Account Details of Government of Karnataka and the Amount to be remitted. The Tenderer shall submit the Printed Challan to its Bank Branch (NEFT enabled) and request for an Account - to - Account Transfer, wherein the money will get transferred from the Tenderer's Bank Account to GOK's Bank Account. The Tenderer shall ensure that NEFT Transfer Instructions are executed and the Funds are wired to the Government of Karnataka's Principal Account before the Last Date for Bid Submission and preferably 24 hours before the Last Date for Bid Submission. If the Tenderer's Bank transfers / wires the money after the Last Date for Bid Submission, the Tenderer's Bid will be liable for rejection. Upon executing the Transfer, the Tenderer's Bank will provide a Reference Number generated by NEFT Software as Confirmation of Transfer, which has to be input by the Tenderer in the Payment Section of its Bid as Payment Confirmation before the Bid is submitted i.e. as a pre requisite for Bid Submission. The Account Number from which the Funds were transferred shall be input in the e - Procurement System as part of its Bid also.

OTC Payment Procedure

If a Tenderer chooses to make Payment of EMD / Tender Processing Fees Over The Counter (OTC) in any of the designated Axis Bank Branches listed in the e - Procurement Website (www.eproc.karnataka.gov.in), the Tenderer will need to log into e - Procurement System, access the Tender for which Bid is being created and then select the OTC Option under the Payment Section and print the Challan shown in that Section. The Printed Challan will have the Unique Bid Reference Number and the Amount to be remitted along with the Challan. The Tenderer can choose to make the Payment either in the form of Cash or in the form of Demand Draft. Cheque Payments will not be accepted. The Tenderer is requested to specifically inform the Bank Officer to input the Unique Bid Reference Number printed in the Challan in the Banking Software. Upon successful Receipt of the Payment, the Bank will provide a 16 Digit Reference Number acknowledging the Receipt of Payment. This 16 Digit Reference Number has to be input by the Tenderer in the Payment Section of its Bid as Payment Confirmation before the Bid is submitted i.e. as a pre requisite for Bid Submission.

13.2 EMD Amount shall be submitted by the Tenderer taking into account of the following

Conditions.

- a. **EMD shall be accepted only in the form of Electronic Cash will be maintained in the Government's Central Pooling Account** at ICICI Bank until the Work is awarded
- b. The Tenderer's Bid will be evaluated only on Confirmation of Receipt of the Payment of EMD as indicated in Sub Clauses 13.1 and 13.2.
- c. Instruments having fixed validity issued as earnest money deposit for the tender shall be

valid for 45 days **beyond** the validity of the tender.

- 13.3 Any tender not accompanied by an acceptable earnest money deposit and not secured as indicated in Sub-Clauses 13.1 and 13.2 above shall be rejected by the Employer as non-responsive.
- 13.4 The earnest money deposit of unsuccessful Tenderers will be returned within 30 days of the end of the tender validity period specified in Sub-Clause 12.1.
- 13.5 The earnest money deposit of the successful Tenderer will be discharged when the Tenderer has signed the Agreement and furnished the required Performance Security.
- 13.6 The earnest money deposit may be forfeited:
- (a) if the Tenderer withdraws the Tender after tender opening during the period of tender validity;
 - (b) if the Tenderer does not accept the correction of the Tender Price, pursuant to Clause 24; or
 - (c) in the case of a successful Tenderer, if the Tenderer fails within the specified time limit to
 - (i) sign the Agreement; or
 - (ii) furnish the required Security deposit

14. Format and signing of Tender

- 14.1 The Electronic Tendering System for the Construction of Work comprises of two Stages (i) Technical Bid and (ii) Financial Bid. The Tenderers are required to submit the Tender Documents in two stages electronically.
- 14.2 The Tender shall contain no Alterations or Additions, except those to comply with instructions issued by the Employer that are duly incorporated.
- 14.3 Each Page uploaded shall be duly signed and sealed by the Tenderer or a Person or Persons duly authorised to sign on behalf of the Tenderer. Such Authorisation shall be indicated by a Written Power - of - Attorney accompanying the Tender. The Corrections, if any, shall be made by striking of and shall be initialed with date.

D. Submission of Tenders

15. Sealing and marking of tenders AS PER E-PORTAL

- 15.1 The Tenderer shall access Tender Documents, fill them and submit the Completed Tender Document as stated in Clause 10 through Website of e - Procurement itself (www.eproc.karnataka.gov.in). The Signed, Sealed and Scanned Copy of all the Documents as stated in Clause 10 shall be attached to the e - Tender Document, failing which the Bid will not be considered. It is the Responsibility of the Tenderer to submit all the Documents pertaining to Eligibility Criteria / Qualification Information / Design Details with due diligence. All the Pages of the Document shall be serially numbered with an Index for ready reference.
- 15.2 No Physical Documents shall be considered. Further, the Tenderer shall submit a Hard Copy of the Technical Bid already submitted through e - Procurement within 2 days of Tender Submission through e - Procurement to the Office of the Executive Engineer, Uttarahalli division during Working Hours. The Tenderers shall also produce all the Original Documents for Verification whenever necessary.
- 15.3 In addition to the identification required in Sub-Clause 15.2, the inner envelopes shall indicate the name and address of the Tenderer to enable the tender to be returned unopened in case it is declared late, pursuant to Clause 17.
- 15.4 If the outer envelope is not sealed and marked as above, the Employer will assume no responsibility for the misplacement or premature opening of the Tender.

16. Deadline for submission of the Tenders AS PER E-PORTAL

- 16.1 Deleted.

CONTRACTOR

Page 18 of 176
EXECUTIVE ENGINEER

16.2 The Employer may extend the deadline for submission of tenders by issuing an amendment in accordance with Clause 9, in which case all rights and obligations of the Employer and the Tenderers previously subject to the original deadline will then be subject to the new deadline.

17. Late Tenders

17.1 Any Tenderer trying to submit the Tender after Deadline will not be accepted in the e - Procurement.

18. Modification and Withdrawal of Tenders

18.1 Tenderers may modify contents of First or Second Covers separately for each Cover or withdraw their Tenders by giving notice in writing before the deadline prescribed in Clause 16.

18.2 Each Tenderer's modification separately for each Cover or withdrawal notice shall be prepared, sealed, marked, and delivered in accordance with Clause 14 & 15, with the outer and inner envelopes additionally marked "**MODIFICATION FOR FIRST/SECOND COVER**" or "**WITHDRAWAL**", as appropriate.

18.3 No Tender may be modified after the deadline for submission of Tenders.

18.4 Withdrawal or modification of a Tender between the deadline for submission of Tenders and the expiration of the original period of Tender validity specified in Clause 12.1 above or as extended pursuant to Clause 12.2 may result in the forfeiture of the earnest money deposit pursuant to Clause 13.

18.5 Tenderers may only offer discounts to, or otherwise modify the prices of their Tenders by submitting Tender modifications in accordance with this clause, or included in the original Tender submission.

E. Tender opening and evaluation

19. Opening of First Cover of all Tenders and evaluation to determine qualified Tenderers:

19.1 The Employer will open the Technical Bids of all the Tenders received in the presence

of the Tenderers or their Representatives who choose to attend on **08.12.2025 @ 11.00** am **at Office of the Executive Engineer,** Uttarahalli division. In the event of the Specified Date of Tender Opening being declared a Holiday for the Employer, the Tenders will be opened at the Appointed Time and Location on the Next Working Day.

19.2 The Tenderers' Names, the Presence or Absence of Earnest Money Deposit (Amount, Format and Validity), the Submission of Qualification Information and such other Information as the Employer may consider Appropriate will be announced by the Employer at the Opening.

19.3 The Employer shall prepare Minutes of the Tender Opening, including the Information Disclosed to those present in accordance with Sub Clause 19.2.

19.4 The Employer will evaluate and determine whether each Tender (a) is accompanied by the Required Earnest Money Deposit as per stipulations in ITT Clause 13.1 and (b) meets the Minimum Qualification Criteria stipulated in ITT Clause 3 and (c) contains the Tenderer's Designs and Drawings on the basis of the Parameters fixed in the Tender Document. The Employer will draw out a List of Qualified Tenderers.

20. Opening of Second Cover of qualified Tenderers and evaluation:

20.1 The Employer will inform all the Qualified Tenderers the Time, Date and Venue fixed for the Opening of the Financial Bid containing the Priced Financial Bid.(also will be E-mailed to concerned) The Employer will open the Priced Financial Bids of Qualified Tenderers at the Appointed Time and Date in the presence of the Tenderers or their Representatives who choose to attend. In the event of the Specified Date of Financial Bid Opening

- being declared a Holiday for the Employer, the Financial Bid will be opened at the Appointed Time and Location on the Next Working Day.
- 20.2 The Tenderers' Names, the Tender Prices, the Total Amount of each Tender, any Discounts, and such other Details as the Employer may consider Appropriate, will be announced by the Employer at the opening. No Tender shall be rejected at Tender Opening.
- 20.3 The Employer shall prepare Minutes of the Priced Financial Bid Opening, including the Information disclosed to those present in accordance with Sub Clause 20.2.

21. Process to be confidential

- 21.1 Information relating to the examination, clarification, evaluation, and comparison of Tenders and recommendations for the award of a contract shall not be disclosed to Tenderers or any other persons not officially concerned with such process until the award to the successful Tenderer has been announced. Any effort by a Tenderer to influence the Employer's processing of Tenders or award decisions may result in the rejection of his Tender.

22 Clarification of Tenders

- 22.1 To assist in the examination, evaluation, and comparison of Tenders, the Employer may, at his discretion, ask any Tenderer for clarification of his Tender, including breakdowns of unit rates. The request for clarification and the response shall be in writing or by cable, but no change in the price or substance of the Tender shall be sought, offered, or permitted except as required to confirm the correction of arithmetic errors discovered by the Employer in the evaluation of the Tenders in accordance with Clause 24.
- 22.2 Subject to sub-clause 22.1, no Tenderer shall contact the Employer on any matter relating to its Tender from the time of the Tender opening to the time the contract is awarded. If the Tenderer wishes to bring additional information to the notice of the Employer, it should do so in writing.
- 22.3 Any effort by the Tenderer to influence the Employer in the Employer's Tender evaluation, Tender comparison or contract award decisions may result in the rejection of the Tenderers' Tender.

23. Examination of Tenders and determination of responsiveness

- 23.1 Prior to the detailed evaluation of Tenders, the Employer will determine whether each Tender; (a) has been properly signed; and; (b) is substantially responsive to the requirements of the Tender documents.
- 23.2 A substantially responsive Tender is one which conforms to all the terms, conditions, and specifications of the Tender documents, without material deviation or reservation. A material deviation or reservation is one (a) which affects in any substantial way the scope, quality, or performance of the Works; (b) which limits in any substantial way, inconsistent with the Tender documents, the Employer's rights or the Tenderer's obligations under the Contract; or (c) whose rectification would affect unfairly the competitive position of other Tenderers presenting substantially responsive Tenders.
- 23.3 If a Tender is not substantially responsive, it will be rejected by the Employer, and may not subsequently be made responsive by correction or withdrawal of the nonconforming deviation or reservation.

24. Correction of errors

- 24.1 Tenders determined to be substantially responsive will be checked by the Employer for any arithmetic errors. Errors will be corrected by the Employer as follows:
- (a) where there is a discrepancy between the rates in figures and in words, the lower of the two will govern¹; and
 - (b) where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by the quantity, the unit rate as quoted will govern.

¹ Clause 25(2) of Chapter VI of KTPP Rules 2000 states that " in case of discrepancy between the price quoted in words and figures, the lower of the two shall be considered".

24.2 The amount stated in the Tender will be adjusted by the Employer in accordance with the above procedure for the correction of errors and, with the concurrence of the Tenderer, shall be considered as binding upon the Tenderer. If the Tenderer does not accept the corrected amount the Tender will be rejected, and the earnest money deposit may be forfeited in accordance with Sub-Clause 13.6 (b).

25. Evaluation and comparison of Tenders

25.1 The Employer will evaluate and compare only the Tenders determined to be substantially responsive in accordance with Clause 23.

25.2 In evaluating the Tenders, the Employer will determine for each Tender the evaluated Tender Price by adjusting the Tender Price as follows:

- (a) making any correction for errors pursuant to Clause 24; and
- (b) making appropriate adjustments to reflect discounts or other price modifications offered in accordance with Sub Clause 18.5.

25.3 The Employer reserves the right to accept or reject any variation, deviation, or alternative offer. Variations, deviations, and alternative offers and other factors which are in excess of the requirements of the Tender documents or otherwise result in unsolicited benefits for the Employer shall not be taken into account in Tender evaluation.

25.4 The estimated effect of the price adjustment conditions under Clause 41 of the Conditions of Contract, during the implementation of the Contract, will not be taken into account in tender Evaluation

25.5 If the tender of the successful tenderer is seriously unbalanced in relation to the Employer's estimate of the cost of the work to be performed under the contract, the Employer may require the Tenderer to produce detailed price analyses for any or all items of the Bill of Quantities, to demonstrate the internal consistency of those prices with the construction methods and schedule proposed. After evaluation of the price analyses, the Employer may require that the amount of the performance security set forth in Clause 29 be increased at the expense of the successful Tenderer to a level

sufficient to protect the Employer against financial loss in the event of default of the successful tenderer under the contract.

F. Award of Contract

26. Award criteria

26.1 Subject to Clause 27, the Employer will award the Contract to the Tenderer whose Tender has been determined to be substantially responsive to the Tender documents and who has offered the lowest evaluated Tender Price, provided that such Tenderer has been determined to be (a) eligible in accordance with the provisions of Clause 2, and (b) qualified in accordance with the provisions of Clause 3.

27. Employer's right to accept any Tender and to reject any or all Tenders

27.1 Notwithstanding Clause 26, the Employer reserves the right to accept or reject any Tender, and to cancel the Tender process and reject all Tenders, at any time prior to the award of Contract, without thereby incurring any liability to the affected Tenderer or Tenderers or any obligation to inform the affected Tenderer or Tenderers of the grounds for the Employer's action

28. Notification of award and signing of Agreement

28.1 The Tenderer whose Tender has been accepted will be notified of the award by the Employer prior to expiration of the Tender validity period by cable, telex, e-mail or facsimile confirmed by registered letter. This letter (hereinafter and in the *Conditions of Contract* called the "Letter of Acceptance") will state the sum that the Employer will pay the Contractor in consideration of the execution, completion, and maintenance of the Works by the Contractor as prescribed by the Contract (hereinafter and in the Contract called the "Contract Price").

28.2 The notification of award will constitute the formation of the Contract, subject only to the furnishing of Security deposit in accordance with the provisions of Clause 29.

28.3 The Agreement will incorporate all agreements between the Employer and the successful Tenderer. It will be kept ready for signature of the successful Tenderer in the office of Employer

CONTRACTOR

Page 24 of 176
EXECUTIVE ENGINEER

- within 30 days following the notification of award along with the Letter of Acceptance. Within 20 days of receipt, the successful Tenderer will sign the Agreement and deliver it to the Employer.
- 28.4 Upon the furnishing by the successful Tenderer of the Performance Security, the Employer will promptly notify the other Tenderers that their Tenders have been unsuccessful.
- 28.5 The defect liability period for various works under the this package work shall be as under:-
- Two year.

29. Security deposit

- 29.1 Within 20 days of receipt of the Letter of Acceptance, the successful Tenderer shall deliver to the Employer a Security deposit in any of the forms given below for an amount equivalent to 5% of the Contract price plus additional security for unbalanced tenders in accordance with Clause 25.5 of ITT and Clause 44 of the Conditions of Contract for all works.:
- Cash or
 - Banker's cheque/Demand draft,/Pay Order in favour of THE Commissioner Bengaluru south city Corporation A/C Executive Engineer, Uttarahalli Division, BSCC, BENGALURU payable at BENGALURU or
 - A bank guarantee in the form given in Section 10; or
 - Specified Small Savings Instruments pledged to Commissioner Bengaluru south city Corporation A/C, Executive Engineer, Uttarahalli Division, BSCC, BENGALURU
- 29.2 If the security deposit is provided by the successful Tenderer in the form of a Bank Guarantee, it shall be issued either by a Nationalized/Scheduled bank.
- 29.3 The security deposit if furnished in cash or demand draft can, if requested, be converted to interest bearing securities at the cost of the contractor.
- 29.4 Failure of the successful Tenderer to comply with the requirements of Sub-Clause 29.1 shall constitute sufficient grounds for cancellation of the award and forfeiture of the Earnest money deposit.

30 Advance Payment and Security:

30.1 Deleted

31. Corrupt or Fraudulent practices

31.1 The BSCC requires that the Tenderers/Suppliers/Contractors, observe the highest standard of ethics during the procurement and execution of such contracts. In pursuance of this policy, BSCC :

- (a) will reject a proposal for award if it determines that the Tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;
- (b) will declare a firm ineligible, either indefinitely or for a stated period of time, to be awarded a BSCC contract if it at any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a BSCC contract.

31.2 Furthermore, Tenderers shall be aware of the provision stated in sub-clause 50.2 of the Conditions of Contract.

SECTION 3: QUALIFICATION INFORMATION

The information to be filled in by the Tenderer hereunder will be used for purposes of computing Tender capacity as provided for in Clause 3 of the Instructions to Tenderers. This information will not be incorporated in the Contract.

1.1 Constitution or legal status of Tenderer [Attach copy]

Place of Registration

(Attach Copy)

Principal place of business:

1.2 Total value of civil engineering construction
2020-21

Works executed and payments received in the last five year
2021-22

(in Rs. Lakhs) Attach Certificate from Chartered Accountant
2022-23.....

CONTRACTOR

Page 27 of 176
EXECUTIVE ENGINEER

24

2024-25

.....

1.3 Work performed as Prime Contractor (in the same name) on works of similar nature over during the five years specified in 1.2 above.

Project Name	Name of Employer	Description of Work	Contract Number	Value of Contract Rs. Lakhs	Date of issue of work order	Specified period of completion	Actual date of Actual date of	Remarks explaining reasons for delay in completion of work
1	2	3	4	5	6	7	8	9

1.4 Quantities of work executed as prime contractor (in the same name) during the last five years specified in 1.2 above:

Year	Name of Work	Name of Employer	Quantity of work performed (cum) ²	Remarks (Indicate contract reference)
------	--------------	------------------	---	---------------------------------------

² Items of work for which data is requested should tally with that specified in ITT Clause

			Road Works	Drains	Culver ts	
2020-21						
2021-22						
2022-23						
2023-24						
2024-25						

1.5 Information on works for which Tenders have been submitted and works which are yet to be completed as on the date of this Tender.

(A) Existing commitments and on-going works:

Descripti on of Work	Plac e & Stat e	Contra ct No. & Date	Name And Addres s of Employ er	Value of Contra ct (Rs. lakhs)	Stipulat ed period of completi on	Value of works remainin g to be complete d (Rs. lakhs) Attach Certifica tes from Engineer s -in- Charge	Anticipat ed date of completi on
1	2	3	4	5	6	7	8

(B) Works for which Tenders already submitted:

CONTRACTOR

Page 29 of 176
EXECUTIVE ENGINEER

Descripti on of Work	Place & State	Name and Address of Employer	Estimat ed value of works (Rs. lakhs)	Stipulat ed period of completi on	Date when decision is expected	Remarks if any
1	2	3	4	5	6	7

1.6. The following items of equipment are considered essential for successfully carrying out the works. The Tenderer should furnish all the information listed below.

Item of Equipment	Requirement ³		Owned	Owned and available		
	No.	Capac ity		Number/ Capacity	Age/ conditio n	Remarks

1.7 Reports on the financial standing of the tenderer, such as profit and loss statements and auditor's reports for the last five years;

1.8 Qualification and experience of the key technical and management personnel in permanent employment with the tenderer and those that are proposed to be deployed on this contract, if awarded.

³ The item of equipment, required number and capacity should match with those specified in ITT Clause 3.3 (a)

- 1.9. Name, address, and telephone, telex, and fax numbers of the Tenderers' bankers who may provide references if contacted by the Employer.
- 1.10 Evidence of access to financial resources to meet the qualification requirement specified in ITT Clause 3.3 (b): Cash in hand, Letter of Credit etc. List them below and attach certificate from the Banker in the suggested format as under:

BANKER'S CERTIFICATE

This is to certify that M/s. is a reputed company with a good financial standing. If the contract for this work, namely (*name of the work*) is awarded to the above firm, we shall be able to provide overdraft/credit facilities to the extent of Rs. to meet the working capital requirements for executing the above contract

Name of the Bank, Senior
Bank Manager with
Signature

Address:

.....

- 1.11 Proposals for subcontracting components of works amounting to more than 20% of the contract price .

Item of Work	Value of Sub-Contract	Identified Sub-Contractor (Name and	Experience of similar work (Attach certificates from the respective Employers.)
--------------	-----------------------	--	--

CONTRACTOR

Page 31 of 176
EXECUTIVE ENGINEER

		address)	
1	2	3	4

1.12 Information on litigations in which the Tenderer is involved:

Other Party (ies)	Employer	Details of dispute	Amount involved	Remarks showing present status

1.13 The proposed methodology and program of construction, backed with equipment planning and deployment, duly supported with broad calculations and quality control procedures proposed to be adopted, justifying their capability of execution and completion of the work as per technical specifications within the stipulated period of completion as per milestones.

SECTION 4: FORMS OF TENDER, LETTER OF ACCEPTANCE, NOTICE TO PROCEED WITH THE WORK AND AGREEMENT FORM

Form of Tender

Description of the Works: **Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures to selected arterial, subarterial and other important roads under Capital Support for Special Infra Projects (CSSIP) (Comprising of 6 works in GO BSCC Sl no 22, 23, 24, 25, 26, 30) Package no CSSIP-UHD-03.**

CONTRACTOR

Page 32 of 176
EXECUTIVE ENGINEER

(To be filled in by the Employer before issue of the Tender document)

Tender

To :

Address

.....Bom

(To be filled in by the Employer before issue of the Tender document)

GENTLEMEN,

We offer to execute the Works described above in accordance with the Conditions of Contract accompanying this Tender for the Contract Price of *[in figures]* (*[in letters]*).⁴

This Tender and your written acceptance of it shall constitute a binding contract between us. We understand that you are not bound to accept the lowest or any Tender you receive.

We undertake that, in competing for (and, if the award is made to us, in executing) the above contract, we will strictly observe the laws against fraud and corruption in force in India namely "Prevention of Corruption Act 1988".

We hereby confirm that this Tender complies with the Tender validity and Earnest money deposit required by the Tender documents.

⁴To be filled in by the Tenderer, together with his particulars and date of submission at the bottom of the Form of Tender

CONTRACTOR

Page 33 of 176
EXECUTIVE ENGINEER

We attach herewith our current income-tax clearance certificate.

Yours faithfully,

Authorized Signature:

Name & Title of Signatory:

Name of Tenderer _____

Address: -----

Letter of Acceptance

(letterhead paper of the Employer)

.....[date]

To:

.....

.....[name and address of the Contractor]

Dear Sirs,

This is to notify you that your Tender dated for execution
of the

.....

..... *[name of the contract and identification number, as given
in the Instructions to Tenderers]* for the Contract Price of Rupees

CONTRACTOR

Page 34 of 176
EXECUTIVE ENGINEER

(.....) [amount in words and figures], as corrected and modified in accordance with the Instructions to Tenderers is hereby accepted by our Agency.

You are hereby requested to furnish Security deposit plus additional security for unbalanced tenders in terms of Clause 25.5 of ITT, in the form detailed in Clause 29.1 of ITT for an amount of Rs..... within 20 days of the receipt of this letter of acceptance valid up to 30 days from the date of expiry of Defects Liability Period i.e. up to and sign the contract, failing which action as stated in Para 29.4 of ITT will be taken.

Yours faithfully,

Authorized Signature

Name and Title of
Signatory

Name of Agency

Issue of Notice to proceed with the work

(letterhead of the Employer)

.....(date)

To

.....

.....

..... (name and address of the Contractor)

Dear Sirs:
CONTRACTOR

Page 35 of 176
EXECUTIVE ENGINEER

Pursuant to your furnishing the requisite security deposit as stipulated in ITT Clause 29.1 and signing of the contract agreement for the construction of (name of the work) a Tender Price of Rs..... , you are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours faithfully,

(Signature, name and title of
signatory

authorized to sign on behalf of
Employer)

Agreement Form

Agreement

This agreement, made the day of 20....., between.....
.....
....[name and address of Employer]
(hereinafter called "the Employer") of the one part and
.....
.....[name and address of contractor] (hereinafter called "the Contractor") of the other part.

Whereas the Employer is desirous that the Contractor execute
.....
..... name and identification number of Contract] (hereinafter called "the Works") and the Employer has accepted the Tender by the Contractor for the execution and completion of such Works and the remedying of any defects therein at a contract price of Rupees.....

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the

CONTRACTOR

Page 37 of 176
EXECUTIVE ENGINEER

remedying the defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz:
- i) Letter of Acceptance;
 - ii) Notice to proceed with the works;
 - iii) Contractor's Tender;
 - iv) Contract Data;
 - v) Conditions of contract (including Special Conditions of Contract);
 - vi) Specifications;
 - vii) Drawings;
 - viii) Bill of Quantities; and
 - ix) Any other document listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of

.....

was hereunto affixed in the presence of:

Signed, Sealed and Delivered by the said

.....

in the presence of:

Binding Signature of Employer

.....

Binding Signature of Contractor

.....

SECTION 5: CONDITIONS OF CONTRACT

Table of Contents

A.	General	Page No.
	1. Definitions	23
	2. Interpretation	23
	3. Law governing contract	24
	4. Employers decisions	24
	5. Delegation	24
	6. Communications	24
	7. Subcontracting	24
	8. Other Contractors	24
	9. Personnel	24
	10. Employer's and Contractor's risks	24
	11. Employer's risks	24
	12 Contractor's risks	25
	13. Insurance	25
	14. Site Investigation Report	25
	15 Query about Contract Data	25
	16 Contractor to construct the Works	25
	17. The Works to be completed by Intended Completion Date	25
	18 Approvals by the Employer	26
	19. Safety	26
CONTRACTOR		

20.	Discoveries	
26		
21.	Possession of the Site	
26		
22.	Access to the Site	
26		
23.	Instructions	
26		
24.	Procedure for resolution of disputes	
26		

B. Time Control

25.	Program	26
26.	Extension of the Intended Completion Date	
27		
27.	Delays ordered by the Employer	
27		
28.	Management meetings	
27		

C. Quality Control

29.	Identifying defects	
27		
30.	Tests	27
31.	Correction of defects	
27		
32.	Uncorrected defects	
27		

D. Cost Control

33	Bill of Quantities (BOQ)	28
34	Variations	28

35.	Payment for Variations	
	28	
36.	Submission of bills for payment	
29		
37	Payments	29
38.	Compensation events	
	29	
39.	Tax	29
40	Price Adjustment	29
41.	Liquidated damages	
	30	
42.	Advance Payments	
	30	
43.	Securities	
30		
44.	Cost of repairs	
	31	

E Finishing of Contract

45.	Completion	
31		
46.	Taking Over	
31		
47.	Final account	
31		
48.	As built drawings and/or Operating and	
Maintenance Manuals	31	
49.	Termination	
31		
50	Payment upon termination	32
51.	Property	32
52.	Release from performance	
32		

F Special Conditions of Contract 33

Conditions of Contract

A. General

1. Definitions

- 1.1 Terms which are defined in the Contract Data are not also defined in the Conditions of Contract but keep their defined meanings. Bold letters are used to identify defined terms.

Bill of Quantities means the priced and completed Bill of Quantities forming part of the Tender.

Compensation events are those defined in Clause 38 hereunder.

The **Completion Date** is the date of completion of the Works as certified by the Employer in accordance with Sub Clause 46.1.

The **Contract** is the contract between the Employer and the Contractor to execute, complete and maintain the Works. It consists of the documents listed in Clause 2.2 below.

The **Contract Data** defines the documents and other information which comprise the Contract.

The **Contractor** is a person or corporate body whose Tender to carry out the Works has been accepted by the Employer.

The **Contractor's Tender** is the completed Tender document submitted by the Contractor to the Employer.

The **Contract price** is the price stated in the Letter of Acceptance and thereafter as adjusted in accordance with the provisions of the Contract.

Days are calendar days; **months** are calendar months.

A **Defect** is any part of the Works not completed in accordance with the Contract.

The **Defects liability period** is the period named in the Contract Data and calculated from the Completion Date.

The **Employer** is the party who will employ the Contractor to carry out the Works.

Equipment is the Contractor's machinery and vehicles brought temporarily to the Site to construct the Works.

The **Initial Contract price** is the Contract Price listed in the Employer's Letter of Acceptance.

The **Intended Completion Date** is the date on which it is intended that the Contractor shall complete the Works. The Intended Completion Date is specified in the Contract Data. The Intended Completion Date may be revised only by the Employer by issuing an extension of time.

Materials are all supplies, including consumables, used by the contractor for incorporation in the Works.

Plant is any integral part of the Works which is to have a mechanical, electrical, electronic or chemical or biological function.

The **Site** is the area defined as such in the Contract Data.

Specification means the Specification of the Works included in the Contract and any modification or addition made or approved by the Employer.

The **Start Date** is given in the Contract Data. It is the date when the Contractor shall commence execution of the works. It does not necessarily coincide with any of the Site Possession Dates.

A **Subcontractor** is a person or corporate body who has a Contract with the Contractor to carry out a part of the work in the Contract which includes work on the Site.

A **Variation** is an instruction given by the Employer which varies the Works.

The **Works** are what the Contract requires the Contractor to construct, install, and turn over to the Employer, as defined in the Contract Data.

2. Interpretation

2.1 In interpreting these Conditions of Contract, singular also means plural, male also means female or neuter, and the other way around. Headings have no significance. Words have their normal meaning under the language of the Contract unless specifically defined. The Employer will provide instructions clarifying queries about the Conditions of Contract.

2.2 The documents forming the Contract shall be interpreted in the following order of priority:

- (1) Agreement
- (2) Letter of Acceptance, notice to proceed with the works
- (3) Contractor's Tender
- (4) Contract Data

CONTRACTOR

Page 44 of 176
EXECUTIVE ENGINEER

(5) Conditions of Contract

(6) Specifications

(7) Drawings

(8) Bill of quantities and

(9) any other document listed in the Contract Data as forming part of the Contract.

3. Law governing contract

3.1 The law governing the Contract is the Laws of India supplanted by the Karnataka Local Acts.

4. Employer's decisions

4.1 Except where otherwise specifically stated, the Employer will decide contractual matters between the Employer and the Contractor .

5. Delegation

5.1 The Employer may delegate any of his duties and responsibilities to other people after notifying the Contractor and may cancel any delegation after notifying the Contractor.

6. Communications

6.1 Communications between parties which are referred to in the conditions are effective only when in writing. A notice shall be effective only when it is delivered (in terms of Indian Contract Act).

7. Subcontracting (Deleted)

7.1 Deleted.

8. Other Contractors

8.1 The Contractor shall cooperate and share the Site with other contractors, public authorities, utilities, and the Employer.

9. Personnel

- 9.1 The Contractor shall employ the technical personnel (of number and qualifications) as may be stipulated by GOK from time to time during the execution of the work. The technical staff so employed shall be available at site as may be stipulated by the Employer.
- 9.2 If the Employer asks the Contractor to remove a person who is a member of the Contractor's staff or his work force stating the reasons, the Contractor shall ensure that the person leaves the Site within seven days and has no further connection with the work in the Contract.

10. Employer's and Contractor's risks

- 10.1 The Employer carries the risks which this Contract states are Employer's risks, and the Contractor carries the risks which this Contract states are Contractor's risks

11. Employer's risks

- 11.1 The Employer is responsible for the excepted risks which are:
- (a) rebellion, riot commotion or disorder unless solely restricted to employees of the Contractor or his Sub-Contractors arising from the conduct of the Works; or
 - (b) a cause due solely to the design of the Works, other than the Contractor's design; or
 - (c) any operation of the forces of nature (in so far as it occurs on the Site) which an experienced contractor:
 - (i) could not have reasonably foreseen; or
 - (ii) could reasonably have foreseen, but against which he could not reasonably have taken at least one of the following measures;
 - (A) prevent loss or damage to physical property from occurring by taking appropriate measures or
 - (B) insure against such loss or damage

12. Contractor's risks

- 12.1 All risks of loss of or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract other than the excepted risks are the responsibility of the Contractor.

13. Insurance:

- 13.1 The Contractor shall prior to commencing the works, effect and thereafter maintain insurances , in the joint names of the

Employer and the Contractor, (cover from the first working day after the Start Date to the end of Defects Liability Period), in the amounts stated in the Contract Data :

- (a) for loss of or damage to the Works, Plants and Materials and the Contractor's equipment;
 - (b) for liability of both Parties for loss, damage, death and injury to third parties or their property arising out of the Contractor's performance of the Contract including the Contractor's liability for damage to the Employer's property other than the Works and
 - (c) for liability of both Parties and of any Employer's representative for death and injury to the Contractor's personnel except to the extent that liability arises from the negligence of the Employer, any Employer's representative or their Employees.
- 13.2 Policies and certificates for insurance shall be delivered by the Contractor to the Employer for his approval before the Start Date. All such insurance shall provide for compensation to be payable to rectify the loss or damage incurred. All payments received from insurers relating to loss or damage shall be held jointly by the Parties and used for the repair of the loss or damage or as compensation for loss or damage that is not to be repaired.
- 13.3 If the Contractor fails to effect or keep in force any of the insurances referred to in the previous sub-clauses or fails to provide satisfactory evidence, policies or receipts, the Employer may without prejudice to any other right or remedy, effect insurance for the cover relevant to such default and pay the premiums due and recover the same as a deduction from any other monies due to the Contractor. If no payments is due, the payment of the premiums shall be a debt due.
- 13.4 Alterations to the terms of an insurance shall not be made without the approval of the Employer.
- 13.5 Both Parties shall comply with any conditions of the insurance policies.

14. Site Investigation Reports:

- 14.1 The Contractor, in preparing the tender, shall rely on any site investigation reports referred to in the Contract data, supplemented by any information available to the Tenderer.

15. Queries about the Contract Data

- 15.1 The Employer will clarify queries on the Contract Data.

16. Contractor to construct the Works

CONTRACTOR

Page 47 of 176
EXECUTIVE ENGINEER

16.1 The Contractor shall construct the Works in accordance with the Specification and Drawings.

17. The Works to be completed by the Intended Completion Date

17.1 The Contractor may commence execution of the Works on the Start Date and shall carry out the Works in accordance with the program submitted by the Contractor, as updated with the approval of the Employer, and complete them by the Intended Completion Date.

18. Approval by the Employer:

18.1 The Contractor shall submit Specification and drawings showing the proposed Temporary Works to the Employer, who is to approve them if they comply with the Specifications and Drawings.

18.2 The Contractor shall be responsible for the design of Temporary Works

18.3 The Employer's approval shall not alter the Contractor's responsibility for design of the Temporary Works.

18.4 The Contractor shall obtain approval of third parties to the design of third parties to the design of the temporary Works where required.

18.5 All Drawings prepared by the Contractor for the execution of the temporary or permanent Works, are subject to prior approval by the Employer before their use.

19. Safety

19.1 The Contractor shall be responsible for the safety of all activities on the Site.

20. Discoveries

20.1 Anything of historical or other interest or of significant value unexpectedly discovered on the Site is the property of the Employer. The Contractor is to notify the Employer of such discoveries and carry out the Employer's instructions for dealing with them.

21. Possession of the Site

21.1 The Employer shall give possession of all parts of the Site to the Contractor. If possession of a part is not given by the date

stated in the Contract Data the Employer is deemed to have delayed the start of the relevant activities and this will be Compensation Event.

22. Access to the Site

- 22.1 The Contractor shall allow the Employer and any person authorized by the Employer access to the Site, to any place where work in connection with the Contract is being carried out or is intended to be carried out and to any place where materials or plant are being manufactured / fabricated / assembled for the works.

23. Instructions

- 23.1 The Contractor shall carry out all instructions of the Employer which comply with the applicable laws where the Site is located.

24. Procedure for resolution of Disputes:

- 24.1 If the Contractor is not satisfied with the decision taken by the Employer, the dispute shall be referred by either party to Arbitration within 30 days of the notification of the Employer's decision.
- 24.2 If neither party refers the dispute to Arbitration within the above 30 days, the Employer's decision will be final and binding.
- 24.3 The Arbitration shall be conducted in accordance with the arbitration procedure stated in the Special Conditions of Contract.

B. Time Control

25. Program

- 25.1 Within the time stated in the Contract Data the Contractor shall submit to the Employer for approval a Program showing the general methods, arrangements, order, and timing for all the activities in the Works.
- 25.2 The Employer's approval of the Program shall not alter the Contractor's obligations. The Contractor may revise the Program and submit it to the Employer again at any time. A revised Program is to show the effect of Variations and Compensation Events.

26. Extension of the Intended Completion Date

26.1 The Employer shall extend the Intended Completion Date if a Compensation Event occurs or a Variation is issued which makes it impossible for Completion to be achieved by the Intended Completion Date.

26.2 The Employer shall decide whether and by how much to extend the Intended Completion Date within 21 days of the Contractor asking the Employer for a decision upon the effect of a Compensation Event or Variation and submitting full supporting information.

27. Delays ordered by the Employer

27.1 The Employer may instruct the Contractor to delay the start or progress of any activity within the Works.

28. Management meetings

28.1 The Employer may require the Contractor to attend a management meeting. The business of a management meeting shall be to review the progress achieved and the plans for remaining work.

28.2 The responsibility of the parties for actions to be taken is to be decided by the Employer either at the management meeting or after the management meeting and stated in writing to be distributed to all who attended the meeting.

C. Quality Control

29. Identifying defects

29.1 The Employer shall check the Contractor's work and notify the Contractor of any Defects that are found. Such checking shall not affect the Contractor's responsibilities. The Employer may instruct the Contractor to search for a Defect and to uncover and test any work that the Employer considers may have a Defect

30. Tests

30.1 If the Employer instructs the Contractor to carry out a test not specified in the Specification to check whether any work has a Defect and the test shows that it does, the Contractor shall pay for

the test and any samples. If there is no Defect the test shall be a Compensation Event.

31. Correction of defects

31.1 The Employer shall give notice to the Contractor of any Defects before the end of the Defects Liability Period, which begins at Completion and is defined in the Contract Data. The Defects Liability Period shall be extended for as long as Defects remain to be corrected.

31.2 Every time notice of a Defect is given, the Contractor shall correct the notified Defect within the length of time specified by the Employer's notice.

32. Uncorrected defects

32.1 If the Contractor has not corrected a Defect within the time specified in the Employer's notice, the Employer will assess the cost of having the Defect corrected, and the Contractor will pay this amount.

D. Cost Control

33. Bill of Quantities (BOQ)

33.1 The BOQ shall contain items for the construction, installation, testing, and commissioning work to be done by the Contractor.

33.2 The BOQ is used to calculate the Contract Price. The Contractor is paid for the quantity of the work done at the rate in the BOQ for each item

34. Variations

34.1 The Employer shall have power to order the Contractor to do any or all of the following as considered necessary or advisable during the progress of the work by him

(a) Increase or decrease of any item of work included in the Bill of Quantities (BOQ);

(b) Omit any item of work;

(c) Change the character or quality or kind of any item of work;

(d) Change the levels, lines, positions and dimensions of any part of the work;

(e) Execute additional items of work of any kind necessary for the completion of the works; and

CONTRACTOR

Page 51 of 176

EXECUTIVE ENGINEER

- (f) Change in any specified sequence, methods or timing of construction of any part of the work.
- 34.2 The Contractor shall be bound to carry out the work in accordance with any instructions in this connection, which may be given to him in writing by the Employer and such alteration shall not vitiate or invalidate the contract.
- 34.3 Variations shall not be made by the Contractor without an order in writing by the Employer, provided that no order in writing shall be required for increase or decrease in the quantity of an item appearing in the BOQ so long as the work executed conforms to the approved drawings.
- 34.4 The Contractor shall promptly request in writing to the Employer to confirm verbal orders and the officer issuing oral instructions shall confirm it in writing within 30 days, failing which the work shall be carried out as though there is no variation. In case variation is approved it shall be accompanied by BOQ, failing which the contractor shall be responsible for deviation if any. Further, approval of Govt. / BSCC has to be obtained for the variation exceeding 5%.

35. Payments for Variations

- 35.1 Payment for increase in the quantities of an item in the BOQ up to 25% of that provided in the Bill of Quantities shall be made at the rates quoted by the Contractor.
- 35.2 For quantities in excess of 125% of the tendered quantity of an item as given in the BOQ, the Contractor shall be paid at the rate entered in or derived from in the Schedule of Rates (applicable for the area of the work and current at the time of award of contract) plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract.
- 35.3 If there is no rate for the additional, substituted or altered item of the work in the BOQ, efforts would be made to derive the rates from those given in the BOQ or the Schedule of Rates (applicable for the area of the work and current at the time of award of contract) and if found feasible the payment would be made at the derived rate for the item plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract
- 35.4 If the rates for additional, substituted or altered item of work cannot be determined either as at 35.1 or 35.2 or 35.3 above, the

Contractor shall be requested to submit his quotation for the items supported by analysis of the rate or rates claimed, within 7 days.

35.5 If the Contractor's quotation is determined unreasonable, the Employer may order the Variation and make a change to the Contract Price which shall be based on Employer's own forecast of the effects of the Variation on the Contractor's costs.

35.6 If the Employer decides that the urgency of varying the work would prevent a quotation being given and considered without delaying the work, no quotation shall be given and the Variation shall be treated as a Compensation Event.

35.7 Under no circumstances the Contractor shall suspend the work on the plea of non-settlement of rates for items falling under this Clause.

36. Submission of bills for payment

36.1 The Contractor shall submit to the Employer monthly bills of the value of the work completed less the cumulative amount paid previously.

36.2 The Employer shall check the Contractor's bill and determine the value of the work executed which shall comprise of (i) value of the quantities of the items in the BOQ completed and (ii) valuation of Variations and Compensation Events.

36.3 The Employer may exclude any item paid in a previous bill or reduce the proportion of any item previously paid in the light of later information.

37. Payments

37.1 Payments shall be adjusted for deductions for advance payments other than recoveries in terms of contract and taxes, at source, as applicable under the law. The Employer shall pay the Contractor on submission of the bill. The contractor shall be liable to pay liquidated damages for shortfall in progress. For progress beyond the agreed programme payment is subject to availability of the grants.

37.2 Items of the Works for which no rate or price has been entered in will not be paid for by the Employer and shall be deemed covered by other rates and prices in the Contract.

38. Compensation events

38.1 The following are Compensation events unless they are caused by the Contractor:

- (a) The Employer does not give access to a part of the Site by the Site Possession Date stated in the Contract Data.
- (b) The Employer orders a delay or does not issue drawings, specifications or instructions required for execution of works on time.
- (c) The Employer instructs the Contractor to uncover or to carry out additional tests upon work which is then found to have no Defects.
- (d) The Employer gives an instruction for dealing with an unforeseen condition, caused by the Employer, or additional work required for safety or other reasons.
- (e) The effect on the Contractor of any of the Employer's Risks.
- (f) The Employer unreasonably delays issuing a Certificate of Completion.
- (g) Other Compensation Events listed in the Contract Data or mentioned in the Contract.

38.2 If a Compensation Event would cause additional cost or would prevent the work being completed before the Intended Completion Date, the Contract Price shall be increased and/or the Intended Completion Date is extended. The Employer shall decide whether and by how much the Contract Price shall be increased and whether and by how much the Intended Completion Date shall be extended.

38.3 As soon as information demonstrating the effect of each Compensation event upon the Contractor's forecast cost has been provided by the Contractor, it is to be assessed by the Employer and the Contract Price shall be adjusted accordingly. If the Contractor's forecast is deemed unreasonable, the Employer shall adjust the Contract Price based on Employer's own forecast. The Employer will assume that the Contractor will react competently and promptly to the event.

38.4 The Contractor shall not be entitled to compensation to the extent that the Employer's interests are adversely affected by the Contractor not having given early warning or not having cooperated with the Employer.

39. Tax

39.1 The rates quoted by the Contractor shall be deemed to be (excluding GST) and including of the sales and other taxes that the Contractor will have to pay for the performance of this Contract. The Employer will perform such duties in regard to the deduction of such taxes at source as per applicable law.

40. Price Adjustment:

40.1 Contract price shall be adjusted for increase or decrease in rates and prices of labour, materials, fuels and lubricants in accordance with the following principles and procedures and as per formulae given in the Contract Data.⁵

- (a) The price Adjustment shall apply for the work done from the date of commencement up to the end of original period of completion or extensions granted by the Employer and shall not apply to work carried out beyond the stipulated period of completion for reasons attributable to the Contractor;
- (b) Price Adjustment shall be admissible from the date of opening of tenders (original or extended)
- (c) The price adjustment shall be determined during each quarter from the formulae given in Contract Data.
- (d) Following expressions and meanings are assigned to the work done during the quarter:

R = Total value of work done during the quarter. It will **exclude** value for works executed under variations for which price adjustment (if any) will be worked out separately based on the terms mutually agreed.

40.2 To the extent that full compensation for any rise or fall in costs to the contractor is not covered by the provisions of this or other Clauses in the Contract, the unit rates included in the contract

⁵ Refer GOK Order No.FD 59 Pro.Cell 2004, Bangalore Dated 26th November 2004

shall be deemed to include amounts to cover the contingency of such other rise or fall in costs.

41. Liquidated damages

- 41.1 The Contractor shall pay liquidated damages to the Employer at the rate per day stated in the Contract Data for each day that the Completion Date is later than the Intended Completion Date (for the whole of the works or the milestone as stated in the Contract Data). The total amount of liquidated damages shall not exceed the amount defined in the Contract Data. The Employer may deduct liquidated damages from payments due to the Contractor. Payment of liquidated damages does not affect the Contractor's liabilities.
- 41.2 If the Intended Completion Date is extended after liquidated damages have been paid, the Employer shall correct any overpayment of liquidated damages by the Contractor by adjusting the next payment of bill.

42. Advance Payments:

Deleted

43. Securities:

- 43.1 The Security deposit (including additional security for unbalanced tenders) shall be provided to the Employer no later than the date specified in the Letter of Acceptance and shall be issued in an amount and form and type of instrument acceptable to the Employer. The Security deposit shall be valid until a date 30 days from the date of expiry of Defects Liability Period and the additional security for unbalanced tenders shall be valid until a date 30 days from the date of issue of the certificate of completion.

44. Cost of Repairs:

- 44.1 Loss or damage to the Works or Materials to be incorporated in the Works between the Start Date and the end of the Defects Correction periods shall be remedied by the Contractor at the Contractor's cost if the loss or damage arises from the Contractor's acts or omissions.

E. Finishing the Contract

45. Completion

- 45.1 The Contractor shall request the Employer to issue a Certificate of Completion of the Works and the Employer will do so upon deciding that the Work is completed.

46. Taking over

- 46.1 The Employer shall take over the Site and the Works within seven days of issuing a certificate of Completion.

47. Final account

- 47.1 The Contractor shall supply to the Employer a detailed account of the total amount that the Contractor considers payable under the Contract before the end of the Defects Liability Period. The Employer shall issue a Defect Liability Certificate and certify any final payment that is due to the Contractor within 90 days of receiving the Contractor's account if it is correct and complete. If it is not, the Employer shall issue within 90 days a schedule that states the scope of the corrections or additions that are necessary. If the Final Account is still unsatisfactory after it has been resubmitted, the Employer shall decide on the amount payable to the Contractor and make payment within 60 days of receiving the Contractor's revised account.

48. As built drawings and /or Operating and Maintenance Manuals

- 48.1 If "as built"(*Completion drawings*) Drawings and/or operating and maintenance manuals are required, the Contractor shall supply them by the dates stated in the Contract Data.
- 48.2 If the Contractor does not supply the Drawings by the dates stated in the Contract Data, or they do not receive the Employer's approval, the Employer shall withhold the amount stated in the Contract Data from payments due to the Contractor.

49. Termination

- 49.1 The Employer may terminate the Contract if the other party causes a fundamental breach of the Contract.

49.2 Fundamental breaches of Contract include, but shall not be limited to the following:

- (a) the Contractor stops work for 45 days when no stoppage of work is shown on the current Program and the stoppage has not been authorized by the Employer;
- (b) Deleted.
- (c) The Contractor becomes bankrupt or goes into liquidation other than for a reconstruction or amalgamation;
- (d) Deleted.
- (e) the Employer gives Notice that failure to correct a particular Defect is a fundamental breach of Contract and the Contractor fails to correct it within a reasonable period of time determined by the Employer;
- (f) the Contractor does not maintain a security which is required;
- (g) the Contractor has delayed the completion of works by the number of days for which the maximum amount of liquidated damages can be paid as defined in the Contract data; and
- (h) if the Contractor, in the judgment of the Employer has engaged in corrupt or fraudulent practices in competing for or in the executing the Contract.

For the purpose of this paragraph : “corrupt practice” means the offering, giving, receiving or soliciting of any thing of value to influence the action of a public official in the procurement process or in contract execution. “Fraudulent practice” means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of the Borrower, and includes collusive practice among Tenderers (prior to or after Tender submission) designed to establish Tender prices at artificial non-competitive levels and to deprive the Borrower of the benefits of free and open competition.”

49.3 When either party to the Contract gives notice of a breach of contract to the Employer for a cause other than those listed under

Sub Clause 49.2 above, the Employer shall decide whether the breach is fundamental or not.

49.4 Notwithstanding the above, the Employer may terminate the Contract for convenience.

49.5 If the Contract is terminated the Contractor shall stop work immediately, make the Site safe and secure and leave the Site as soon as reasonably possible.

50. Payment upon Termination

50.1 If the Contract is terminated because of a fundamental breach of Contract by the Contractor, the Employer shall prepare bill for the value of the work done less advance payments received up to the date of the bill, less other recoveries due in terms of the contract, less taxes due to be deducted at source as per applicable law and less the percentage to apply to the work not completed as indicated in the Contract Data. Additional Liquidated Damages shall not apply. If the total amount due to the Employer exceeds any payment due to the Contractor the difference shall be a debt payable to the Employer.

50.2 If the Contract is terminated at the Employer's convenience or because of a fundamental breach of Contract by the Employer, the Employer shall prepare bill for the value of the work done, the reasonable cost of removal of Equipment, repatriation of the Contractor's personnel employed solely on the Works, and the Contractor's costs of protecting and securing the Works and less advance payments received up to the date of the certificate, less other recoveries due in terms of the contract, and less taxes due to be deducted at source as per applicable law and make payment accordingly.

51. Property

51.1 All materials on the Site, Plant, Equipment, Temporary Works and Works are deemed to be the property of the Employer, if the Contract is terminated because of a Contractor's default.

52. Release from performance

- 52.1 If the Contract is frustrated by any event entirely outside the control of either the Employer or the Contractor the Employer shall certify that the Contract has been frustrated. The Contractor shall make the Site safe and stop work as quickly as possible after receiving this certificate and shall be paid for all work carried out before receiving it and for any work carried out afterwards to which commitment was made

F. Special Conditions of Contract

1. Labour :

The Contractor shall, unless otherwise provided in the Contract, make his own arrangements for the engagement of all staff and labour, local or other, and for their payment, housing, feeding and transport.

The Contractor shall, if required by the Employer, deliver to the Employer a return in detail, in such form and at such intervals as the Employer may prescribe, showing the staff and the numbers of the several classes of labour from time to time employed by the Contractor on the Site and such other information as the Employer may require.

2. Compliance with labour regulations :

During continuance of the contract, the Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the State or Central Government or local authority and any other labour law (including rules), regulations, bye laws that may be passed or notification that may be issued under any labour law in future either by the State or the Central Government or the local authority. The Contractor shall keep the Employer indemnified in case any action is taken against the Employer by the competent authority on account of contravention of any of the provisions of any Act or rules made there under, regulations or notifications including amendments. If the Employer is caused to pay or reimburse, such amounts as may be necessary to cause or observe, or for non-observance of the provisions stipulated in the notifications/bye laws/Acts/Rules/regulations including amendments, if any, on the part of the Contractor, Employer shall have the right to deduct any money due to the Contractor including

his amount of security deposit. The Employer shall also have right to recover from the Contractor any sum required or estimated to be required for making good the loss or damage suffered by the Employer.

The employees of the Contractor in no case shall be treated as the employees of the Employer at any point of time.

3. Protection of Environment:

The contractor shall take all reasonable steps to protect the environment on and off the Site and to avoid damage or nuisance to persons or to property of the public or others resulting from pollution, noise or other causes arising as a consequence of his methods of operation. During continuance of the contract, the contractor shall abide at all times by all existing enactments on environmental protection and rules made there under, regulations, notifications and bye-laws of the State or Central Government, or local authorities and any other law, bye-law, regulations that may be passed or notification that may be issued in this respect in future by the State or Central Government or the local authority.

4. Arbitration (Clause 24)

4.1 The procedure for arbitration shall be as follows:

- (a) In case of dispute or difference arising between the Employer and the Contractor relating to any matter arising out of or connected with this agreement it shall be settled in accordance with the Arbitration and Conciliation Act 1996. The disputes or differences shall be referred to a Sole Arbitrator. The Sole Arbitrator shall be appointed by agreement between the parties; failing such agreement, by the Appointing Authority (any one of the Organizations as per list enclosed in Annexure)
- (b) Arbitration proceedings shall be held at....., Karnataka state (to be filled in by the Employer before issue of the Tender Documents),
- (c) The cost and expenses of arbitration proceedings will be paid as determined by the Arbitrator. However the expenses incurred by each party in connection with the preparation, presentation, etc., shall be borne by each party itself.
- (d) Performance under the contract shall continue during the arbitration proceedings and payments due the Contractor by the Employer shall not be withheld, unless they are the subject matter of the arbitration proceedings.

5. In the case of the death of a Contractor after executing the agreement / commencement of the work, his legal heir, if an

eligible registered Contractor and willing can execute and complete the work at the accepted tender rates irrespective of the cost of the work.

6. The Contractor Should procure Bitumen from MRPL /IOCL and produce invoice for procurement of Bitumen along with work bills. No payments will be made without such invoices.
7. Mix Designs for Concrete and Asphalt work shall be got approved by Chief Engineer before commencement of Work.
8. The Contractor shall execute the work in minimum two shifts (Day & Night) for speedy completion of work and to minimize inconvenience to public.
4. The Tender Documents uploaded in the e - Procurement Website by the Employer, Tender Terms arrived at during Process of Clarifications together with the Letter of Acceptance thereof, shall constitute a Binding Contract between the Successful Tenderer and the Employer and shall form the Foundation of the Rights and Obligation of both the Parties.
5. The Several Documents forming the Contract are to be taken as mutually explanatory of one another, Detailed Drawings being followed in preference to Small Scale Drawings and Figured Dimensions in preference to the Measured Ones. Special Conditions shall be followed in preference to General Conditions / Clauses of the Contract. Particular Specifications shall be followed in preference to General Specifications applicable to the Contract.
6. In case of Discrepancy / Inconsistency between the Description in the Scope of Works, Specifications, Nomenclature of Items and / or the Drawings, Conditions of Contract, Qualification Document and if there are Varying or Conflicting Provisions made in any Document forming Part of the Contract, the Employer shall be the Deciding Authority with regard to the Intention / Interpretation of the Document and his Decision shall be final and binding on the Contractor without any reservations.
7. Any Error in Description or any Omissions there from, shall not vitiate the Contract or release the Contractor from the Execution of the whole or any part of the Works comprised therein according to Drawings and Specifications or from any of his Obligations under the Contract.
8. Time is the Essence of the Contract and it shall be clearly understood that the Contractor is bound to complete the Work in every respect within the Intended Completion Period as stated in the Contract Data.

9. Drawings to be kept at Site

The Required Sets of the Drawings as approved by the Employer shall be kept by the Contractor at the Site and the same shall at all reasonable time be available for Inspection and Use by the Employer and his approved Representative and any other person authorized by the Employer in writing.

10. Inspection of Works

In addition to the Provisions of Relevant Clauses of the Contract, the Work shall also be open to Inspection by the Employer and his approved Representative. The Contractor shall at all times during the Usual Working Hours and at all times at which Reasonable Notices of the Intention of the Employer or his approved Representative as stated above to visit the Works shall have been given to the Contractor, either himself be present to receive the Orders and Instructions or have a responsible Site Engineer duly accredited in writing, to be present for that Purpose.

16. Foreign Exchange

It shall be clearly understood that no Foreign Exchange shall be made available for the Purpose of Equipment, Plants, Machinery or Materials of any kind or any other Items / Purposes required to be carried out in Execution of the Work. It shall be clearly understood that no Foreign Exchange required for importing Equipments, Materials for Tools, Plants and Machinery, etc. that may be required in carrying out the Work, even from the Rupee Payment Country will be made available.

17. Night Work

For Completing the Work well within the Intended Completion Period, the Contractor might be required to work in two or more Shifts (including Night Work) and no Claim whatsoever shall be entertained on this account, notwithstanding, the Fact that the Contractor will have to pay to the Labours and other Staff engaged directly or indirectly on the Work according to the Provisions of the Labour Regulations and the Agreement entered into and for Extra Amounts towards any other Reason. None of the Permanent Works shall be carried out during Night or on Authorized Public Holidays without the permission in writing of the Employer except when Work is unavoidable or absolutely necessary for the Safety of Life, Property or Work in which case the Contractor shall immediately advise the Employer accordingly, provided that the Provisions of this Condition shall not be Applicable in the case of any Work which is customary to carry out by Rotation or in Double Shift.

18. Existing Services

Existing Drains, Pipes, Cables, Overhead Wires, Sewer Lines, Water Lines and similar Services encountered in the Course of the

Execution of the Work shall be protected / maintained against the Damage by the Contractor. The Contractor shall not store Materials or otherwise occupy any part of the Site in a manner likely to hinder the Operation of such Services. In case Temporary Shifting of such Services is required to facilitate the Work, the Contractor at no Extra Cost shall do the same.

The Respective Departments in coordination with the Employer shall carry out Shifting of Major Services. The Decision as whether the Service in Question is Major or not, will be at the Discretion of the Employer. The Contractor will, however, be required to provide all help to ensure that the Work is carried out smoothly.

19. All Works pertaining to Services including Rerouting / Diversion of Services, Routine Testing, Installation, etc. embracing in one or more than one Process shall be subject to Examination and Approval to each Stage thereof by the Employer or concerned Departments as would be notified by the Employer or his approved Representative when such Stage is ready. In default of such Notice, the Employer shall be entitled to appraise the Quantity and the Extent thereof and the Decision of the Employer or his approved Representative in this regard shall be final and binding.
20. No Work shall be covered or put out of View without the approval of the Employer or his approved Representative and the Contractor shall afford Full Opportunity for Examination of such Services before these are permanently installed or extended thereof as per Site Requirement.
21. No Accommodation is available at the Site of Work for Office, Residence, Labour, Store, etc. and the Contractor has to make his own Arrangement and no Claim whatsoever on this account shall be entertained.
22. The Contractor shall make his own arrangement for the Disposal of the Spoils from the Works to such Place where the same shall not cause Nuisance and shall be acceptable to the Authorities concerned.
23. The Execution of any Items of Work where any Incidental Work is actually required but not specifically stated in the Tender Document, it is to be understood that the Amount quoted by the Contractor shall cover such Charges also and nothing extra on account of such Incidental Charges, if any, shall be paid.
24. The Contractor shall make his own arrangement at his own Cost for the Provision of Telephone Facilities at the Site of Works or at any other place.

25. The Electric and Water Connections to be obtained for use of the Work under the Contract are subject to the following Conditions.
- a. The Contractor shall make his own arrangement for Electricity and Water Supply. However, the Employer will assist the Contractor to get Power from the concerned Department at the Contractor's Cost.
 - b. The Employer shall in no way be Responsible for any Delay in getting the Electric Connection and Water and no Claim on this account whatsoever, shall be entertained. It shall be clearly understood that the Contractor has to make his own Arrangement for Generators for use before the Electric Connection is made available and also to be used as a Standby Arrangement in case of Power Failure, etc. or in the case of Disconnection of Electric Supply by the concerned Department for any reason.
26. No Payment will be made to the Contractor for Damage caused by Rains, or other Natural Calamities or Accidents or Acts of God, during the Execution of the Works and no such Claim on this account will be entertained.
27. The Contractor is required to submit Rates of all Items he has used to derive the Tendered Price inclusive of Cost of all Labour, Materials, Plant, Machinery, Equipments, Carriage and other Inputs, Taxes, Royalties, etc.
28. The Contractor shall maintain in Good Condition all Work till the Completion of entire Work allotted to him. From the Commencement of the Work to the Completion of the same, the Work is to be under the Contractor's Charge. The Contractor is to be held Responsible for and to make good all Injuries, Damages and Repairs, rendered necessary by Fire, Rain, Traffic, Floods or other Causes. The Employer shall not be held Responsible, for any Claims for Injuries to Personal Workmen or for Structural Damage to Property happening from any Neglect, Default, Want of Proper Care or Misconduct on the Part of the Contractor or of any other of his authorized Representatives in his Employment during the Execution of the Work. The Compensation, if any, shall be paid directly to the Department / Authority / Persons concerned, by the Contractor at his own Cost.
29. The Contractor will take all Necessary Measures for the Safety of Traffic and Workers during Construction and provide, erect and

maintain such Barricades, including Signs, Markings, Flags, Lights and Skilled Flagmen, as necessary, all around the Excavation / Construction Area and at such Intermediate Points, as directed by the Employer including the Proper Identification of the Construction Areas. He shall be Responsible for all Damages and Accidents on account of Construction and other Relevant Activities. Nothing shall be paid extra on account of above.

The Temporary Warning Signs / Lamps shall be installed at all Barricades during the Hours of Darkness and kept lit there at all times during these hours and nothing shall be paid extra.

Barricading and Safety Requirements are very Important Aspects at this Portion of the Road. The above Provisions shall be followed strictly and at no time the Construction / Excavation Areas are to be left Unbarricaded or without Red Lamps during the Hours of Darkness. Failure to comply with the Requirements mentioned in the Preceding Paragraphs shall be deemed to be a Breach of Contract on the Part of the Contractor for which the Contractor shall be Liable to action under Relevant Clauses / Conditions of the Agreement.

In addition to other Actions being taken for such Breach of Contract, the Contractor shall be liable to pay compensation @ Rs. 1000/- per Sqm of Area left Unbarricaded.

The Employer shall give Notice to the Contractor for such Barricade and the Contractor shall comply with the same within one day of such Notice failing which he shall be liable to pay the above Compensation and Actions for the said Breach of Contract. The Decision of the Employer in respect of the above shall be final and binding.

The Contractor shall use every Reasonable Means to prevent any of Roads, Bridges communicating with or on the Routes to the Site from being damaged by any Traffic of the Contractor or any of his Sub Contractors and in particular, shall select Routes and Vehicles to avoid such Unnecessary Damages.

30. Safety of Workers

In respect of all Labour directly or indirectly employed in the Work for the Performance of the Contractor's Part of this Agreement, the Contractor shall at his own Expense arrange for the Safety Provisions as per Indian Standard Safety Codes shown below and shall at his own Expense provide all Facilities in connection there

with. In case, the Contractor fails to make Arrangement and provide Necessary Facilities as aforesaid, he shall be liable to pay Rs. 10000/- per Day for each day of Delay from the Date of Notice issued to the Contractor on this regard and in addition the Employer shall be at liberty to make Arrangement and provide Facilities as aforesaid and recover the Cost incurred on that behalf from the Contractor, and no Claims whatsoever shall be entertained.

- i. IS: 3696 (Part I) - 1966 Safety Code for Scaffolds and Ladders
 - ii. IS: 3696 (Part II) - 1966 Safety Code for Scaffolds and Ladders, Part II Ladders
 - iii. IS: 3764 - 1966 Safety Code for Excavation Work
 - iv. IS 4081 - 1967 Safety Code for Blasting and Drilling Operations
 - v. IS: 4138 - 1977 Safety Code for Working in Compressed Air
 - vi. IS: 5121 Safety Code for Piling and other Deep Foundations
 - vii. IS: 5916 - 1970 Safety Code for Construction involving Use of Hot Bituminous Materials
 - viii. IS: 7293 - 1974 Safety Code for Working with Construction Machinery
 - ix. IS: 7969 -1975 Safety Code for Storage and Handling of Building Materials
 - x. Any other Code and / or as per directions of the Employer.
31. The Employer shall have Full Powers to send Workmen and employ on the Premises to execute Fittings and other Work not included in the Contract. For whole Operations, the Contractor is to afford every Reasonable Facility during Ordinary Working Hours provided that such Operations shall be carried on in such a manner as not to impede the Progress of the Work included in this Contract in the opinion of the Employer.

32. The Contractor shall conduct his Work so that not to interfere with or hinder the Progress or Completion of the Work being performed by other Contractors, Piece Workers or by the Employer and shall as far as possible arrange his Work and shall place and dispose the Operations of the other Contractors, Piece Workers, or of the Employer. The Contractor shall arrange his Work with that of the others in an Acceptable Manner and shall perform it in Proper Sequence to the complete Satisfaction of the Employer at the Contractor's own Cost.
33. The Contractor shall assume all Liabilities, Financial or otherwise in connection with his Contract and shall protect and save the Employer from any and all Damages and Claims that may arise because of the Presence and Operations of others working on or near the Site. The Contractor shall assume all Responsibilities for all Work not completed or accepted because of the Presence and Operations of other Contractors or Piece Workers or of the Employer.
34. At the time of Construction, the Contractor shall embed all Electrical / other Fixtures like Base Plates, Brackets, Conduits, etc. for Street Lighting, etc. as per the Directions of the Employer. Nothing Extra whatsoever will be payable on this account.
35. For execution of any Items of Work where Incidental Works such as Bailing out Water, Shoring, etc. are actually required but not specifically stated in the Tender, it is to be understood that the Amount quoted by the Contractor shall cover such Charges also and nothing Extra on account of such Incidental Charges, if any, shall be paid.
36. **No Waiving of Legal Rights and Powers**

The Employer shall not be precluded or stopped from taking any Measurements and Framing of Estimates or Detaining any Certificates made either before or after the Completion and Acceptance of the Work and Payment, from showing the True Amount and Character of the Works Performed and Materials furnished by the Contractor and from showing that any such Measurements, Estimates or Certificates Untrue or incorrectly made and that the Employer shall not be precluded or stopped from recovering from the Contractor and such Damages as it may be sustained by Reasons of his Failure to comply with the Terms and Conditions of the Contract. Neither the Acceptance by the

Employer nor any Payment for Acceptance of the whole or any part of the Work nor any Extension of Time nor any Possession taken by the Employer shall operate as a Waiver of any Portion of the Contract or any Power herein reserved or of any Risk to Damage. A Waiver of any Breach of the Contract shall not be held to be a Waiver of any other or subsequent Breach.

37. The Tenderers shall also mention with their Tender Documents the Name of their Project Managers, Work Managers, Graduate Engineers who shall be engaged in this Work. The Biodata of such Engineers / Managers are to be enclosed with the Tender Documents.
38. The Tenderers may specify the Number and Category of each type of Skilled Personnel to be deputed by the Contractors. It may clearly be stated as to whether such Skilled Persons are under the Employment of the Tenderers or are still to be appointed by them. The Number of Skilled and Unskilled Persons to be employed shall be in agreement with the Programme of Work submitted by the Tenderers and discussed elsewhere in the Tender Documents.
39. The Employer might deploy Project Management Consultant (PMC) for Design Checking and Approval, Supervision, Quality Control, Progress Monitoring, etc. The Contractor shall abide by the Instructions / Suggestions given by the PMC for the successful completion of the Project.
40. **Interference with Traffic and Adjoining Properties**
 - a. All Operations necessary for the Execution and Completion of the Works and the Remedying of any Defects therein shall, so far as Compliance with the Requirements of the Contract Permits, shall be carried out so that not to interfere unnecessarily or improperly with the following.
 - i. The Convenience of the public, or
 - ii. The Access to, Use and Occupation of Public or Private Roads and Footpaths or of Properties whether in the Possession of the Employer or of any other person
 - b. In case any Operation connected with the Traffic necessitates Diversion, Obstruction or Closure of any Road, Railway or any other Right of Way, the Approval of the Employer and the Concerned Authorities shall be obtained well in advance by the Contractor.

41. Avoidance of Damage to Roads

The Contractor shall use every Reasonable Means to prevent any of the Roads, Bridges communicating with or on the Routes to the Site from being damaged, injured by any Traffic of the Contractor or any of his Sub Contractors and in particular, shall select Routes, choose and use Vehicles and restrict and distribute Loads so that any such Extraordinary Traffic as will inevitably arise from the Moving of Materials, Plant, Contractor's Equipment or Temporary Works from and to the Site shall be limited, as far as reasonably possible, and so that no Unnecessary Damage or Injury may be occasioned to such Roads and Bridges.

42. Transport of Contractor's Equipment or Temporary Works

- a. The Contractor shall be Responsible for and shall pay the Cost of Strengthening any Bridges or altering or improving any Road communicating with or on the Routes to the Site to facilitate the Movement of Contractor's Equipment or Temporary Works and the Contractor shall indemnify and keep indemnified the Employer against all Claims for Damage to any such Road or Bridge caused by such movement, including such Claims as may be made directly against the Employer, and shall negotiate and pay such Claims arising solely out of such Damage.
- b. If it is found necessary for the Contractor to move one or more Loads of Heavy Constructional Plant and Equipment, Materials or Parts of Units of Work over Roads, Highways, Bridges on which such Oversized and Overweight Items are not normally allowed to be moved, the Contractor shall obtain Prior Permission from the Concerned Authorities. Payments for complying with the Requirements, if any, for Protection of or Strengthening of the Roads, Highways or Bridges shall be made by the Contractor and such expenses shall be deemed to be included in his Contract Price.

43. Personal Protective Equipment

The Contractor shall at all times keep and maintain an adequate supply of suitable Personal Protective Equipment, which shall be readily available for use at all times on the site and would include but not to be limited to the following Items.

- Safety Helmets.
- Hearing Protection.
- Respiratory Protection.

- Eye Protection.
- Protective Gloves.
- Safety Footwear.
- High Visibility Clothing conforming to BS EN 471 Class 3 Standards.

All Sites shall be designated as HARD HAT and SAFETY BOOTS SITES and as such an adequate supply of Safety Helmets and Safety Boots shall be kept available for use by all Staffs, Workers and Authorised Visitors to the Sites.

The Contractor shall remove from the Site any worker who consistently refuses to wear the appropriate Personal Protective Equipment.

All Workmen at Site shall be provided with Safety Helmets and Yellow / Orange Jackets. Workmen required on Site during night hours shall be provided with Fluorescent Yellow Jackets with Reflective Lopes. Workers employed on mixing Asphaltic Materials, Cement, Lime Mortars, Concrete, etc. shall be provided with Protective Footwear, Protective Goggles. Those engaged in handling any Material, which is injurious to the eyes, shall be provided with Protective Goggles. Those engaged in Welding Works shall be provided with Welder's Protective Eye Shield. Stone Breakers shall be provided with Protective Goggles and Protective Clothing and seated at sufficiently safe intervals.

44. First Aid

The Contractor shall maintain, at every Work Place, in a readily accessible place First Aid Appliances including an adequate supply of Sterilised Dressings, Bandages, Sterilised Cotton Wool, Eye Irritation Sterile Solution, Disposable Gloves, Ointments for Burns / Cuts, Pressure Dressings, Paper Towels, General Purpose Medicines, etc. as prescribed in the Factory Rules of the State in which the Work is being carried out. The Appliances shall be kept in good order and in large work places. They shall be placed under the charge of the Safety Officer deputed by the Contractor for this Work and the Safety Officer shall be readily available during Working Hours. In each Site Office and Location one Person, suitably trained in First Aid, shall be available at all Working Hours for the purpose of attending to emergencies.

45. Fire Precautions

The Contractor shall be responsible for supplying and maintaining adequate Fire Precaution Facilities on all the Work Sites. The following minimum Standards shall be adhered to.

- The Contractor shall ensure that specially trained personnel are available to deal with fires due to Electrical Causes, Gas Explosions, etc.
- A Good Standard of Housekeeping shall be maintained at all times on the Sites.
- No Accumulations of Rubbish shall be allowed to gather.
- Combustible Scrap and other Construction Debris shall be disposed off site on day - to - day basis. If Scrap is to be burnt on site, the burning site shall be specified and located at a distance no less than 50m from any Construction Work or any other Combustible Materials.
- Signage shall be erected at prominent positions showing the correct use of Portable First Aid Fire Extinguishers.
- Emergency Plans and Fire Evacuation Plans shall be prepared and issued. Mock Drills shall be held on a regular basis to ensure the Effectiveness of the Arrangements.

46. Fire Fighting Equipment

At various locations around the Site, clearly visible Fire Points shall be established for use in an Emergency and each Fire Point should have available as a minimum the following type of Equipment.

- Dry Powder Extinguisher.
- Water Type Extinguisher.
- Bucket of Sand.

Recharging of Fire Extinguishers and their Proper Maintenance should be ensured and as a minimum should meet Indian National Standards.

The Telephone Number of the Local Fire Brigade along with other Emergency Numbers (Hospital, Police Stations, Ambulance, etc.) shall be displayed near each telephone on Site. Supervisors and Workmen at the Site should be trained in the Use of Fire Fighting Equipment provided at the Site.

47. Storage of Flammable Liquid

All Flammable Liquids shall be kept in a Secure Fire Resistant Store protected from Electrical Sparks, Welding Sparks, Open

Flames and Smoking. Only such amounts of Flammable Liquids shall be issued as are required for immediate use.

Cans for carrying Flammable Liquids shall be leak proof and properly stoppered and clearly marked "Flammable Liquid".

Rags soaked in Paints, Kerosene and other Flammable Liquids shall be disposed of daily under supervision. Large quantities of such rags shall not be allowed to accumulate.

All Diesel Fuel Storage Tanks shall be banded around in order to control any Spillage or Leakage that may occur.

"No Smoking" Signs shall be prominently displayed at all areas where Flammable Materials are stored.

48. Defect Liability Period

The Defect Liability is 2 years

49. Release of Performance Security

Performance Security shall be released only after satisfactory completion of Defect Liability Period.

50. Site Office

The Contractor shall provide and maintain Furnished Site Office at the Project Location for the Supervisory Staff of the Employer and his approved Representative.

It shall have minimum 40 Sqm of Floor Area and shall include all Items like Electric Supply, Electrical Items, Telephones, Lights, Fans and Complete Wiring, Drinking Water Supply and Hygienic Toilet Facilities completed along with Furniture as per the Specification given in **Section 100 of MoRT&H, Specifications for Road and Bridge Works (Fourth Revision)**.

51. Field Laboratory

The Contractor shall provide and maintain adequately equipped Field Laboratory as required for Site Control on the Quality of Material and the Works. It shall have a minimum of 40 Sqm Area. The Field Laboratory shall be located as directed by the Employer

- or his approved Representative. It shall be provided with Amenities like Water Supply, Electric Supply, etc. The Laboratory will have all Services, Furniture, Equipments, etc. as per the Specification given in **Section 100 of MoRT&H, Specifications for Road and Bridge Works (Fourth Revision)**. Materials used during the work should be tested periodically as per standards and the test report should be certified with the concerned implementing officer
52. The Right to carry out the Work either in Conformity with or in a Manner entirely different from the Terms of this Tender Document that may be considered most suitable before or subsequent to the Receipt of Tenders due to Exigencies of Work is reserved with the Employer.
53. **Progress of Work**
The Contractor shall give the Employer on the 4th Day of each Month a Progress Report of the Work done during the Previous Month.
- The Progress of Work will be reviewed periodically by the Employer with the Contractor and Shortfalls, if any sorted out, the Contractor shall thereupon take such Action that may be necessary to bring back his Work to Schedule without any Additional Cost to the Employer by employing Overtime Operations, increasing the Number of Shifts, Capacity of the Equipment or otherwise as directed by the Employer and nothing shall be paid extra.
54. In the case of the death of a Contractor after executing the Agreement / Commencement of the Work, his Legal Heir, if an Eligible Registered Contractor and willing, can execute and complete the work at the accepted Tender Rates irrespective of the Cost of the Work.
55. The Contractor should display at the work spot a display board indicating The approved name of work, Estimate Cost, Approved Tender Amount, Duration of work, Name of the Agency with Phone no. and the phone no. of BSCC implementing officers.
56. **The Employer shall have the right to verify all the Men and Machinery Details / Documents submitted by the Tenderer at any point of time during Technical Evaluation of the Tender Document.**
57. The Contractor should furnish PERT Chart showing the schedule of work and should get it approved from concerned Competent Authority

CONTRACTOR

Page 74 of 176

EXECUTIVE ENGINEER

Annexure:

**LIST OF ORGANIZATIONS WHO ARE CONSIDERED AS
APPOINTING AUTHORITY FOR APPOINTMENT OF
ARBITRATORS⁶**

1. Indian Council of Arbitration, New Delhi;
2. International Centre for Alternative Disputes Resolution (India);
3. Indian Roads Congress;
4. Indian Building Congress;
5. Indian Institute of Bridge Engineers;
6. Indian Institute of Public Health Engineers;
7. Institute of Water Works

⁶ Add any other Organization considered suitable.

SECTION 6: CONTRACT DATA

Items marked "N/A" do not apply in this Contract.

The following documents are also part of the Contract:
Clause Reference

- **The Schedule of Operating and Maintenance Manuals**
[48]
- **The Methodology and Program of Construction**
[25]
- **Site Investigation Reports** **[14]**
- **The Schedule of Key and Critical Equipment to be deployed**
on the work as per agreed program of construction.
[25]

The Employer is:

Name: The Commissioner **[1.1]**

Address: BSCC, Jayanagara Zone, BSCC Building, 2nd
Floor, ,9th main,Jayanagar 2nd Block, Bangalore-560011

Name of authorized Representative: Office of the Executive
Engineer, Uttarahalli Division,

Bengaluru South City Corporation,Amruth nagara-
Konankunte Main road, Soudamini Layout,
Bengaluru-62.

**The name and identification number of the Contract is
[1.1]**

Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures to selected arterial, subarterial and other important roads under Capital Support for Special Infra Projects (CSSIP) (Comprising of 6 works in GO BSCC Sl no 22, 23, 24, 25, 26, 30) Package no CSSIP-UHD-03

The Works consist of Improvements to Drain & Road

The start date shall be the date of issue of notice to proceed with the work. [1.1]

The Intended Completion Date for the whole of the Works is 11 months with the following milestones [17, 26]

Milestone dates:

Physical works to be completed Period from the date of issue of Notice to proceed with the work

Milestone 1 i.e Financial Progress for Rs.944.92 Lakhs within 4 Months from the date of work order

Milestone 2 i.e Financial Progress for Rs.708.69 Lakhs within 4 Months from the date of work order

Milestone 3 i.e Financial Progress for Rs.708.69 Lakhs within 3 Months from the date of work order

**The Site Possession Date is:⁷ Date of work order
[21]**

**The Site is located at Bangalore south, [1.1]
and is defined in drawings**

The Defects Liability Period is 2 Years ⁸. [31]

⁷ At the time of preparation of the tender document give the period after the issue of work order, when the site would be made available to the contractor, for example 'one week after the issue of work order'

	Type of Cover	Minimum cover for Insurance ⁹
(i)	Works and of Plant and materials	The sum stated in the Agreement plus 20%
(ii)	Loss or damage to equipment	Full replacement cost
(iii)	Loss or damage to property of Third Party	Full replacement cost
(iv)	Personal injury or death insurance (a) for Third Party ¹⁰	
	(b) for Contractor's employees or labour	In accordance with the statutory requirements applicable to Karnataka

Price Adjustment Formula;¹¹ (DELETED)
[40]

The liquidated damages for the whole of the works are Rs.236230/-(amount) per day¹² and that for the milestones are as under:

⁸ The period should depend up on the period required for testing of the work. In case of building it could be 12 months (passing of one rainy season); for pipe laying work, tanks, water retaining structures, the time required for testing; for canals, lining works, the passing of one monsoon or running of canal whichever is lower; roads and highways passing of one monsoon (12 months)

⁹ Employer to specify as per requirement. Exclusions if any should also be specified.

¹⁰ Specify an appropriate figure. For normal works it could be Rs.20 lakhs to cover 4 persons @Rs.5 lakhs each.

¹¹ The Formula has some normal components. It should be changed if need be to suit the nature of the work.

For Milestone 1:Rs 94492/- per day

[41]

For Milestone 2:Rs 70869/-per day

For Milestone 3:Rs 70869/- Per day

The maximum amount of liquidated damages for the whole of the works

[41]

is Ten percent of final contract price.

The amounts of the advance payment are: Deleted
[42]

¹³The date by which “as-built”¹⁴ drawings (in scale 1:1000 ¹⁵) in 2 sets are required is within

30 days of issue of certificate of completion of Whole or Section of the

Work as the case may be.

[48]

¹⁶The date by which Operating and Maintenance Manuals are required is

within 30 days of issue of certificate of completion of Whole or Section of the

Work as the case may be.

[48]

The amount to be withheld for failing to supply “as built” drawings or supply of

Operation and Maintenance Manuals by the date required is Rs 50,000/-

(The amount should be sufficient to get the completion drawings or Operating and

¹² The amount is usually computed on the basis of 0.1% of the contract price per day. The amount has to be specified as a round figure nearest to the hundred.

¹³ Score out whichever is not applicable.

¹⁴ Completion drawings

¹⁵ Specify an appropriate scale

¹⁶ Score out which ever is not applicable.

Maintenance Manuals prepared by alternative agency in case the contractor fails to submit.) [48]

The following events shall also be fundamental breach of the contract: [49.2]

1. The contractor has contravened Sub-clause 7.1 and Clause 9 of CC.

The percentage to apply to the value of the work not completed representing

the Employer's Additional cost for completing the Works shall be 30 percent (30%) . [50.1]

(Change if need be. It should be sufficient to get the balance of works completed by alternative agency.)

SECTION 7: SPECIFICATIONS

(MORTH & H and SR)

SECTION 8: DRAWINGS

Enclosed Separately

CONTRACTOR

**Page 80 of 176
EXECUTIVE ENGINEER**

SECTION 9: BILL OF QUANTITIES

Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures to selected arterial , subarterial and other important roads under Capital Support for Special Infra Projects(CSSIP) (Comprising of 6 Works In GO BSCC Sl no 22,23,24,25,26,30) Package no CSSIP-UHD-03						
BOQ						
Estimate Amount :				2977.00 Lakhs		
Sl . N o.	G O N o	Description of Item	Unit	Total Quan tity	Rate in Rs	Total Amount in Rs
1		Removing and refixing Drain Cover slabs (B S Slab and RCC slab) and pointing in CM (1:3) as directed by the Engineer in Charge of the work (excluding GST and Area Leading Charges)	Sqm	2204 6.01		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		8780. 85		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road		2027. 76		

CONTRACTOR

Page 82 of 176
EXECUTIVE ENGINEER

		from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		2163. 00		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		1945. 35		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		2679. 00		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain		4450. 05		

CONTRACTOR

Page 83 of 176
EXECUTIVE ENGINEER

		improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
2		Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of Buildings & bridges and such simillar works in all kinds of soils, as per drawing and technical specifications,including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.In all kinds of soils Depth upto 1.5 m	Cu m	1039 4.40		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		2957. 76		

CONTRACTOR

Page 84 of 176
EXECUTIVE ENGINEER

	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		1158.72		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		1752.60		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		1131.84		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail		1128.00		

		Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		2265.48		
3		Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work In all kinds of soils Depth upto 3 m	Cu m	750.75		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena		0.00		

CONTRACTOR

Page 86 of 176
EXECUTIVE ENGINEER

		agrahara to Koli farm gate)				
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		750.75		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From				

		Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
3		Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead. By Mechanical Means Cement Concrete Grade M-15 & M-20	Cu m	80.10		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		0.00		

	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		0.00		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		80.10		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail				

		Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
4		Dismantling of kerb stone by manual means and disposal of dismantled material with all lifts and lead	Mtr	2310.00		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		0.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		2310.00		

24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj				

CONTRACTOR

Page 91 of 176
EXECUTIVE ENGINEER

		Apartment)				
5		Removing and resetting of precast kerb stones fixed with CM 1:3 fixed and finished in line as per direction of Engineer in charge. (The cost of PCC shall be paid extra)	Mtr	1432 5.60		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		5013. 70		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		1746. 50		
	25	Improvements to existing asphalted road by resurfacing		1412. 70		

CONTRACTOR

Page 92 of 176

EXECUTIVE ENGINEER

		with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		1997.50		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		4155.20		
6		Providing and laying in position Cement Concrete Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS	Cum	402.97		

CONTRACTOR

Page 93 of 176
EXECUTIVE ENGINEER

		Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications.				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		100.95		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		94.27		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station		42.82		

CONTRACTOR

Page 94 of 176
EXECUTIVE ENGINEER

		to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		38.05		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		37.91		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		88.98		
7		Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and	Cum	966.18		

CONTRACTOR

Page 95 of 176
EXECUTIVE ENGINEER

		fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:2:4 Using 20 mm nominal size graded crushed coarse aggregates				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		194.10		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		118.29		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain		177.68		

CONTRACTOR

Page 96 of 176
EXECUTIVE ENGINEER

		improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		115.54		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		115.15		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		245.43		
8		Providing and laying in position Cement Concrete for	Cum	214.50		

CONTRACTOR

Page 97 of 176
EXECUTIVE ENGINEER

		levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		0.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		214.50		

CONTRACTOR

Page 98 of 176
EXECUTIVE ENGINEER

24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj				

		Apartment)				
9		Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancillary operations complete as per drawing and technical specification	Ton ne	12.87		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		0.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		12.87		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain				

CONTRACTOR

Page 100 of 176

EXECUTIVE ENGINEER

		improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
1		Providing and laying 100mm thick pre-cast cover slabs over	Sqm	5010.99		

CONTRACTOR

Page 101 of 176

EXECUTIVE ENGINEER

0		Road side drains / utility ducts / Rain water harvesting pit of width not exceeding 1000 mm using M20 concrete reinforced with TMT bars Fe 550 @ 6kg/ m2, slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drainage of surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc, Complete.				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		462.15		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		1349.04		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain		927.00		

CONTRACTOR

Page 102 of 176

EXECUTIVE ENGINEER

		improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		648.45		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		141.00		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		1483.35		
1		Providing and fixing precast reinforced cement concrete	Sqm	103.54		

CONTRACTOR

Page 103 of 176

EXECUTIVE ENGINEER

1		covering siabs of 23cm thick made out of M25 with OPC cement 340kgs/cum, with 20 mm downsize graded metal coarse aggregates @ 0.70cum and fine aggregates & 0.74 cum with superplasticizers, machine mixed, including providing and removing centering, shuttering, strutting, propping etc., for edges of slabs with TMT steel (Fe 500) cost & reinforcement charges, including pointing wauth CM 1:3, finishing as required with cost of all matenals, labour, all lead and lift, HOM of machinery, curing including cost of reinforcement etc complete				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		12.10		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main		28.08		

		road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		5.04		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		38.88		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		10.80		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km		8.64		

		(From Begur Koppa Police station road to SNN raj Apartment)				
1 2		Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	2436.74		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		1812.76		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on				

CONTRACTOR

Page 106 of 176

EXECUTIVE ENGINEER

		Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		251.58		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		128.00		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		244.40		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder				

CONTRACTOR

Page 107 of 176

EXECUTIVE ENGINEER

		formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
1 3		Supplying and installation of Composite Fiber reinforced Polymer water Gully grating with bottom chamber of appropriate size of 450x450mm and load bearing capacity 40MT(D400 Load capacity)of approved bond confirming to BSEN-124:1994/IS1726.Gully grating should have minimum 30% of water entrance area that clear opening of chamber. It shall give top abrasion resistance layer of decorative dark grey finish.The cover should have a beam design at the bottom with thickness in the centre of minimum of 125mm to 150mm at the centre and should be without any reinforcement of steel or any other metal not be used in construction of product.The chamber should have no filler or reinforcement of any kind of metal and a 150mm dia cutout.The chamber has one circular cut of 200mm dia.It shall also confirm Permanent set criterion as per BSEN-124/IS 1726.Product should be tested	Eac h	36.00		

CONTRACTOR

Page 108 of 176
EXECUTIVE ENGINEER

		in lab for load capacity and permanent set with cost of all materials, transportation, loading and unloading charges etc. Complete excluding GST.				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		10.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		5.00		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		8.00		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder		8.00		

CONTRACTOR

Page 109 of 176

EXECUTIVE ENGINEER

		formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		2.00		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		3.00		
1 4		Providing, laying and jointing HDPE pipes of specified grade and conforming to IS 4984-2016 with latest ammendments and conveying to work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials with	Mtr	82.00		

CONTRACTOR

Page 110 of 176

EXECUTIVE ENGINEER

		electrofusion welding, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bedns, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. complete. NOTE: Upto 110mm dia Coil shall be used. HDPE Grade PE100-PN 3.0,200mm dia				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		36.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP		3.00		

		Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		14.40		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		20.80		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		6.00		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road		1.80		

		from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
1 5		Removing & Resetting existing Heavy Duty Cobble/Interlocking stones/Pavers of thickness 60/75/80/100mm using Cement and 40mm thick sand bed (average thickness) and compacting with plate vibrator to achieve final desired compaction & setting of paver to its final level , including cost of materials, labour and usage charges of machinery complete as per specifications. (The cost of new paver/stones required shall be added separately)	Sqm	9027.40		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		4621.50		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP				

		Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		1740.90		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		832.00		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		1833.00		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road				

		from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
1 6		Providing and laying 60mm thick factory made precast M-30 grade Cement Concrete Paver Block as per IRC SP 63:2018 & IS 15658 for Cycle Tracks & Pedestrian Footpaths of approved shape and colour, laid in required pattern and including over 30mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-incharge. (WMM/WBM Base to be paid separately if necessary as per relevant technical specification).	Sqm	1634 8.40		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		1386 4.50		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP				

CONTRACTOR

Page 115 of 176
EXECUTIVE ENGINEER

		Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		1424.90		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		448.00		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		611.00		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road				

		from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
1 7		Providing S&S RCC SPUN / VIBRATED CAST PIPES (REINFORCED) pipes NP-3 Class conforming to IS:458-1988 with latest amentments using ordinary portland cement, for sanitary works and conveying to work site, rolling and lowering into trenches, laying true to line and level including loading and unloading at both destinations and jointing of pipes and specials, perfect linking of joints with jack to correct position including cost of jointing materials, i.e, rubber rings conforming to IS: 5382 for S&S RCC pipes, with all leads and lifts as directed and giving necessary hydraulic test as per ISS to the required pressure and commissioning etc. complete. (Contractor will make his own arrangements for procuring water for testing). Before the execution of the work, the contractor shall carry out the Survey. RCC NP3 Class pipe of 300 mm Dia	M	2128.65		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain		2128.65		

CONTRACTOR

Page 117 of 176

EXECUTIVE ENGINEER

		improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)				
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain				

CONTRACTOR

Page 118 of 176
EXECUTIVE ENGINEER

		improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
18		Providing Vertical drain appropriate size of 1.05x1.05m.The chamber has Two circular cut of 250 mm dia.The Item Including Excavation, Cement Concrete(M25), Reinforcement,and Top Cover Grating.Product should be tested in lab for load capacity and permanent set with cost of all materials, transportation,loading and unloading charges etc.Complete excluding GST.	Eac h	5.00		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta		5.00		

CONTRACTOR

Page 119 of 176
EXECUTIVE ENGINEER

		road from (From Kalena agrahara to Koli farm gate)				
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road				

CONTRACTOR

Page 120 of 176
EXECUTIVE ENGINEER

		(Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
1 9		Providing, laying and jointing HDPE pipes of specified grade and conforming to IS 4984-2016 with latest ammendments and conveying to work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials with electrofusion welding, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub	Mtr	34.50		

CONTRACTOR

Page 121 of 176
EXECUTIVE ENGINEER

		ends, flanged sets, bedns, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. complete. NOTE: Upto 110mm dia Coil shall be used. HDPE Grade PE100-PN 3.0,250mm dia				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		34.50		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				

	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
20		Fabricating and Placing in Position 125mm dia Bollards 850 mm high of required shape,with ISA 45x45x5mm welded at bottom and embedded 250mm in bitumen/Concrete Pavement at specified spacing with all leads	Kgs	2500.00		

CONTRACTOR

Page 123 of 176

EXECUTIVE ENGINEER

		and lift complete as per specifiaction & as directed by the Engineer incharge of the work.Excluding GST				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		2500.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety				

CONTRACTOR

Page 124 of 176

EXECUTIVE ENGINEER

		measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
2 1		Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and	Nos	1397 6.00		

CONTRACTOR

Page 125 of 176
EXECUTIVE ENGINEER

		lift,transportation etc.,complete as directed by the Engineer in Charge of the work (excluding GST and Area Leading Charges)				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		2054.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		5191.00		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		1717.00		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain		1834.00		

CONTRACTOR

Page 126 of 176

EXECUTIVE ENGINEER

		improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		783.00		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		2397.00		
22		Painting Two Coats on New Concrete Surfaces Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces	Sqm	8258.00		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety		2375.20		

CONTRACTOR

Page 127 of 176
EXECUTIVE ENGINEER

		measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)				
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		924.00		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		1030.00		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		895.20		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety		940.00		

CONTRACTOR

Page 128 of 176

EXECUTIVE ENGINEER

		measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		2093.60		
2 3		Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Manual Means In area of light jungle	100 m2	117.12		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta		0.00		

		road from (From Kalena agrahara to Koli farm gate)				
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		36.21		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road				

CONTRACTOR

Page 130 of 176
EXECUTIVE ENGINEER

		(Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		80.91		
23		Dismantling of Flexible pavements and disposal of dismantled materials and stacking serviceable and unserviceable materials separately By Mechanical Means Bituminous course	Cum	1334.16		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		619.02		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road				

CONTRACTOR

Page 131 of 176
EXECUTIVE ENGINEER

		from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		247.5 0		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		256.1 4		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		211.5 0		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain				

CONTRACTOR

Page 132 of 176

EXECUTIVE ENGINEER

		improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
24		Milling of existing Bituminous surface to a specified depth up to 40mm using Milling machine including disposal of removed material	Sqm	104405.14		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		12930.64		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		10259.50		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40		20837.50		

		km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		1636 4.50		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		1974 0.00		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		2427 3.00		
2 5		Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of	Cu m	7024. 49		

CONTRACTOR

Page 134 of 176

EXECUTIVE ENGINEER

		soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work. In all kinds of soils upto 300 mm depth				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		349.13		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		1939.05		

CONTRACTOR

Page 135 of 176
EXECUTIVE ENGINEER

	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		1125.23		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		1767.37		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		532.98		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj		1310.74		

CONTRACTOR

Page 136 of 176
EXECUTIVE ENGINEER

		Apartment)				
26		Providing and laying of sand/Artificial sand/Manufactured sand including all materials ,labour,HOM of Machinery,Lighting,Gaurding, barricading,and Maintenance, of Diversion with all leads and lifts complete as per specifiaction & as directed by the Engineer incharge of the work.Excluding GST	Cum	2601.66		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		129.31		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		718.17		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety		416.75		

CONTRACTOR

Page 137 of 176

EXECUTIVE ENGINEER

		measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		654.58		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		197.40		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		485.46		
27		Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam	Cum	5910.34		

CONTRACTOR

Page 138 of 176

EXECUTIVE ENGINEER

		specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density.				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		2189.19		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		897.71		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station		779.24		

CONTRACTOR

Page 139 of 176
EXECUTIVE ENGINEER

		to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		946.23		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		491.15		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		606.83		
28		Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of	Sqm	13008.31		

CONTRACTOR

Page 140 of 176
EXECUTIVE ENGINEER

		0.70 kg/m2 using mechanical means.				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		646.53		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		3590.83		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		2083.75		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From		3272.90		

		Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		987.00		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		2427.30		
29		Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.20 kg/m² on the prepared bituminous surface cleaned with mechanical broom	Sqm	170288.24		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena		65865.26		

		agrahara to Koli farm gate)				
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		1025 9.50		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		2083 7.50		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		2536 4.98		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From		2368 8.00		

		Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		2427 3.00		
3 0		Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects. Dense Graded Bituminous Macadam Grading - II for traffic <20 MSA	Cu m	2135. 85		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder		64.65		

CONTRACTOR

Page 144 of 176

EXECUTIVE ENGINEER

		formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)				
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		512.98		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		364.66		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		450.02		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder		197.40		

CONTRACTOR

Page 145 of 176

EXECUTIVE ENGINEER

		formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		546.14		
31		Stone Matrix Asphalt Providing and laying Stone Matrix Asphalt (SMA) using crushed aggregates of specified grading, premixed with Modified Bituminous Binder containing Stabilizer additive (Pellitized Cellous fiber at 0.3% on loose fibre basis) on the weight of total mix in the batch and filler(Hydrated lime dust @ 2% of weight of aggregates, transporting the Hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired	Cum	2579.36		

		compaction as per clause 515 of MORTH V revision using 120 TPH capacity with Sensor paver Sma -40 mm to 50 mm compacted thickness with 5.8 % Vg-30 Bitumen				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		2579.36		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder				

CONTRACTOR

Page 147 of 176

EXECUTIVE ENGINEER

		formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
3 2		Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to	Cu m	3658. 98		

CONTRACTOR

Page 148 of 176

EXECUTIVE ENGINEER

		the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects Bituminous Concrete Grading II for traffic <20 MSA				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)				
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		410.38		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		833.50		

	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		654.58		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		789.60		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		970.92		
33		Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass	Sqm	6551.50		

CONTRACTOR

Page 150 of 176

EXECUTIVE ENGINEER

		beads @ 250 g/m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes.				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		2401.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		482.80		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		925.00		

	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		782.65		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		881.25		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		1078.80		
34		Supplying and Fixing of Molded Shank Raised PavementMarkers / Cat's Eye made of polycarbonate and ABS mouldedbody and reflective panels with micro prismatic lens capable ofproviding total internal	nos	2518.00		

CONTRACTOR

Page 152 of 176

EXECUTIVE ENGINEER

		reflection of the light entering the lensface and shall support a load of 16000 kg tested in accordance to ASTM D 4280 Type H and complying to Specifications of Category A of MORTH Circular No RW/NH/33023/10-97 DO III Dt 11.06. 1997. The height, width and length shall not exceed 50 mm, 100 mm and 102 +/- 2 mm and with minimum reflective area of 13 cm² on each side and the slope to the base shall be 35 +/- 5 degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19 +/- 2 mm and height not less than 30 +/- 2 mm) from the body is to be a minimum value of 500 Kg. Fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin based adhesive as per manufacturer's recommendation and complete as directed by the engineer. The contractor shall submit a two year warranty for satisfactory field performance including stipulated retro-reflectance of the reflecting panel, to the Engineer.				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder		458.00		

CONTRACTOR

Page 153 of 176

EXECUTIVE ENGINEER

		formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)				
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		131.00		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		1334.00		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		155.00		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder		147.00		

CONTRACTOR

Page 154 of 176

EXECUTIVE ENGINEER

		formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		293.00		
35		Plain Cement Pavement Quality M30 grade Concrete (RMC) with OPC & GGBS laid without Paver Construction of un-reinforced plain cement concrete pavement using RMC M-30 grade with OPC @ 270 kg/m³ and GGBS@ 90 kg/m³ (75:25 proportion) as per approved mix design procedure and thickness as per design, over a prepared sub base. The superplastisiser confirming to IS 9103-1999 Reaffirmed-2008 ,Coarse aggregates and Fine aggregate confirming to IS:383-2016, transported to site, laid in approved fixed side form work (steel channel, laying and	Cu m	1504.80		

CONTRACTOR

Page 155 of 176

EXECUTIVE ENGINEER

		fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work). Spreading the concrete with shovels, rakers and compacted using needle, suitable plate vibrator and finished in a continuous operation including provision of separation membrane and Hessian cloth finishing to lines and grades complete including cost of all materials, labour, all lead & lift, loading charges as per specification & direction of Engineer - incharge of the work. (Groove cutting shall be paid seperately)				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		617.40		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		217.26		

	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		202.50		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		256.14		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		211.50		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj				

CONTRACTOR

Page 157 of 176
EXECUTIVE ENGINEER

		Apartment)				
3 6		Cold Plastic Paint Providing and applying Cold plastic paint two component rolled on surfacing material solvent free, high build two pack seamless,tough,skid resistant, material with property of attaining 2mm thickness in single coat application white(or as required colour)based on glass and colour retaining acrylic cross linking resin system for coloured road surfacing including surface cleaning and cost of all material etc. complete. (All inclusive on bitumen or concrete surface) work shall carried out as per IRC 35-2015 clause 2.2)	Sqm	232.5 0		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		95.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP				

CONTRACTOR

Page 158 of 176
EXECUTIVE ENGINEER

		Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)		80.00		
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		57.50		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road				

		from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
3 7		Chevron Boards Supply and installation of retro- reflective Chevron signboards of 600x450mm made out of cube corner micro prismatic grade sheeting confirming to Type XI standards of IRC:67:2022 & ASTM D 4956-09 specification & fixed over 3 mm thick Aluminium Composite Panel sheet having minimum 0.30 mm thick aluminum skin on both sides & fixed over back support frame of 25x25x 3mm MS angle frame. Supported on 75 mm dia OR 75x75x6mm Mild steel with clear height of not less than 2.1 m from the ground level to the bottom of the Sign board & 60 cm below ground level. The sign post should be painted with one coat of red oxide paint and two coats of synthetic enamel paint of black and white colour with bands of 30 cm height, firmly fixed to the ground by means of foundation with M 20 grade cement, concrete foundation size of 45 cm x 45 cm x 60 cm including cost & conveyance of all materials, equipment,machinery & Labour with all leads and lifts for satisfactory completion of	Nos	4.00		

CONTRACTOR

Page 160 of 176
EXECUTIVE ENGINEER

		the work as directed by Engineer incharge.				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		4.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From				

		Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
38		Rumble Strips:Provision of 15 nos rumble strips covered with premix bituminous carpet, 15-20 mm high at center, 250 mm wide placed at 1 m center to center at approved locations to control speed, marked with white strips of road marking paint.	Sqm	352.50		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety		352.50		

CONTRACTOR

Page 162 of 176
EXECUTIVE ENGINEER

		measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)				
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety				

CONTRACTOR

Page 163 of 176
EXECUTIVE ENGINEER

		measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
39		Retro-Reflectorised Traffic Signs:Providing and fixing of retro- reflectorised cautionary, mandatory and informatory sign as per IRC:67:2022 made of Class C Type XI retro reflective sheeting fixed over 2 mm thick aluminium sheeting vide clause 801.3, 3mm/4mm thick Aluminium composite material sheet depending on the size of the sign fixed over the back support frame of min 25 x 25 x 3mm angle mounted on a mild steel circular pipe 65 NB, 3.2mm thickness firmly fixed to the ground by means of properly designed foundation with M25 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved	Eac h	4.00		

		drawing.The sign shall be maintained as per section 12 of IRC:67:2022. (i) 120 cm equilateral triangle				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agraphara to Koli farm gate)		4.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety				

		measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
40		Retro-Reflectorised Traffic Signs:Providing and fixing of retro- reflectorised cautionary, mandatory and informatory sign as per IRC:67:2022 made of Class C Type XI retro reflective sheeting fixed over 2 mm thick aluminium sheeting vide clause 801.3, 3mm/4mm thick Aluminium composite material sheet depending on the size of the sign fixed over the back support frame of min	Eac h	4.00		

CONTRACTOR

Page 166 of 176

EXECUTIVE ENGINEER

		25 x 25 x 3mm angle mounted on a mild steel circular pipe 65 NB, 3.2mm thickness firmly fixed to the ground by means of properly designed foundation with M25 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing. The sign shall be maintained as per section 12 of IRC:67:2022. (xi) 60 mm x 50 mm rectangular				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena aghara to Koli farm gate)		4.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund				

CONTRACTOR

Page 167 of 176

EXECUTIVE ENGINEER

		road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
4 1		Retro-Reflectorised Traffic Signs:Providing and fixing of retro- reflectorised cautionary, mandatory and informatory	Eac h	5.00		

CONTRACTOR

Page 168 of 176
EXECUTIVE ENGINEER

		sign as per IRC:67:2022 made of Class C Type XI retro reflective sheeting fixed over 2 mm thick aluminium sheeting vide clause 801.3, 3mm/4mm thick Aluminium composite material sheet depending on the size of the sign fixed over the back support frame of min 25 x 25 x 3mm angle mounted on a mild steel circular pipe 65 NB, 3.2mm thickness firmly fixed to the ground by means of properly designed foundation with M25 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing. The sign shall be maintained as per section 12 of IRC:67:2022. (xv) 90 cm high octagon				
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		5.00		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km				

		(From Begur road to BBMP Office Nyanapahalli Main road)				
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)				
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS				
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety				

CONTRACTOR

Page 170 of 176
EXECUTIVE ENGINEER

		measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)				
42		Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge to the appropriate disposal area.	Cum	17418.89		
	22	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Baannerghatta road from (From Kalena agrahara to Koli farm gate)		3306.89		
	23	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Devarachikkanalli Main road from Ch. 0.00 to Ch. 1.30 km (From Begur road to BBMP Office Nyanapahalli Main road)		3097.77		
	24	Improvements to existing asphalted road by resurfacing with proper camber, shoulder		2877.83		

CONTRACTOR

Page 171 of 176

EXECUTIVE ENGINEER

		formation, side drain improvement and road safety measures on Begur tank bund road from Ch. 0.00 to Ch. 1.40 km (From Begur police station to AECS B Block)				
	25	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road from Ch. 3.00 to Ch. 4.00 km (From Mahaveer ranches apartment to Slum Quarters)		2899.21		
	26	Improvements to existing asphalted road by resurfacing with proper camber, shoulder formation, side drain improvement and road safety measures on Hosa road (Service Road) from (From Kempegowda Statue to Jail Junction) LHS & RHS		1660.98		
	30	Improvements to existing asphalted road by resurfacing and providing one strengthening layer of asphalt with proper camber, shoulder formation, side drain improvement and road safety measures on Begur koppa road from Ch. 0.00 to Ch. 2.9 km (From Begur Koppa Police station road to SNN raj Apartment)		3576.22		

Note:

- (1) Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities (refer: ITB Clause 11.2 and CC Clause 37.2).
- (2) Unit rates and prices shall be quoted by the Tenderer in Indian Rupees.
- (3) Where there is a discrepancy between the rate in figures and words, the lower of the two will govern. [ITT Clause 24.1(a)]
- (4) Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity, the unit rate quoted shall govern [ITT Clause 24.1 (b)]
- (5) Rates quoted by tenderer are excluding GST but including all other applicable taxes.

SECTION 10: FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT

To: *[name of Employer]*
..... *[address of Employer]*

WHEREAS *[name and address of Contractor]*
(hereinafter called "the Contractor") has undertaken, in pursuance of Contract
No. dated : to execute
[name of Contract and brief description of Works] (hereinafter called "the
Contract");

AND WHEREAS it has been stipulated by you in the said Contract that the
Contractor shall furnish you with a Bank Guarantee by a recognized bank for the
sum specified therein as security for compliance with his obligations in
accordance with the Contract;

AND WHEREAS we have agreed to give the Contractor such a Bank Guarantee;

NOW THEREFORE we hereby affirm that we are the Guarantor and responsible
to you, on behalf of the Contractor, up to a total of Rs. *[amount of
guarantee]*

¹⁷ Rupees.....*[in
words]*, and we undertake to pay you, upon your first written demand and without
cavil or argument, any sum or sums within the limits of

¹⁷ An amount shall be inserted by the Guarantor, representing the percentage of the Contract
Price specified in the Contract

*[amount of guarantee]*¹⁸ as aforesaid without your needing to prove or to show grounds or reasons for your demand for the sum specified therein.

We hereby waive the necessity of your demanding the said debt from the Contractor before presenting us with the demand.

We further agree that no change or addition to or other modification of the terms of the Contract or of the Works to be performed there under or of any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liability under this guarantee, and we hereby waive notice of any such change, addition or modification.

This guarantee shall be valid until 30 days from the date of expiry of the Defects Liability Period.

Signature and seal of the guarantor _____

Name of Bank _____

Address _____

Date _____

¹⁸ An amount shall be inserted by the Guarantor, representing the percentage of the Contract Price specified in the Contract

